

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22330-00-00
Spot: S2N2NW Sec/Twnshp/Rge: 19-8S-22W
4290 feet from S Section Line, 3960 feet from E Section Line
Lease Name: QUINT C Well #: 1
County: GRAHAM Total Vertical Depth: 3640 feet

Operator License No.: 6139
Op Name: BOYER, JAY C.
Address: PO BOX 511
HAYS, KS 67601

PROD Size: 4.5 feet: 3640
SURF Size: 8.625 feet: 228

#118³⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/21/2005 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: HAROLD BELLERIVE Company: BOYER, JAY C. Phone: (785) 625-3556

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel with 500# hulls.
Casing leak - fluid 200' from surface.
Ran tubing to 2100' to plug.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2005 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 3108'.
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled tubing to 1760'.
Allied pumped 88 sxs cement with 200# hulls - cement circulated.
PTOH. Squeezed with 12 sxs cement.
Max. P.S.I. 600#. S.I.P. 600#.
Hooked up to backside and pumped 75 sxs cement.
Max. P.S.I. 100#. S.I.P. 50#.

RECEIVED
MAR 07 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

10

Signed Richard Williams

(TECHNICIAN)

INVOICED

DATE 3.8.05

INV. NO. 2005061246

Form CP-2/3

FEB 28 2005

A & M OIL OPERATIONS

1901 B. E. 24TH

HAYS, KS. 67601

#C-1 QUINT

19-8-22W


C S/2 N/2 NW

CONTR R & C DRILLING

CTY GRAHAM

GEOL JAMES DILLIE

FIELD HILL CITY EAST



ELV 2136 KB SPD 10/16/86 CARD ISSUED 1/8/87

2131 GL DRLG COMP 10/21/86

IP P 147 BOPD, NW

LKC 3550-3558

LOG	Tops	Depth/Datum
SC	1761+	375
TOP	3139	1003
TOR	3380	1244
LANS	3396	1260
RTD	3600	1464

API 15-065-22,330

8 5/8 " 228, 4 1/2 " 3640

NO CORES

DST (1) 3538-3600 (LANS I&J) / 60-60-60-60, 700' GIP, REC
 410' PURE OIL, 100' GSY MCO (5% G, 65% OIL, 30% M), 248'
 GSY MCO (5% G, 75% OIL, 20% M), 62' MCO (50% OIL, 50%
 M), SIP 108-705#, FP 152-184 / 206-673#, HP 1876-1865#
 MICT - CO, PF (LKC) 3550-3558, W / 4 SPF, AC 5000 GAL (28%
 REG), SWB DWN, SO, POP, P 147 BOPD, NW, 11/8/86

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS