

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22182-00-00
Spot: SESWNE Sec/Twnshp/Rge: 34-13S-20W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: STORM Well #: 5
County: ELLIS Total Vertical Depth: 3840 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

PROD Size: 5.5 feet: 3830 175 SX CMT
SURF Size: 8.625 feet: 207 175 SX CMT

124⁸⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2005 2:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RICHARD L WALLGREN SR Company: HANSEN, DANE G. - TRUST Phone: (785) 689-4816

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls - 12 sxs gel spacer.
DV at 1505' w/375 sxs.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2005 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Hooked up to the annulus - instant pressure.
Swaged onto 5 1/2" - mixed and pumped 50 sxs cement with 500# hulls,
followed with 12 sxs gel spacer.
Topped off with 165 sxs cement.
Max. P.S.I. 1000#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3676	3680		
3657	3660		
3646	3649		
3568	3572		
3548	3554		
3519	3522		


RECEIVED
MAR 07 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____



(TECHNICIAN)

INVOICED

DATE

3-8-05

Form CP-2/3

INV. NO.

2005061248

MAR 03 2005

THE DANE G. HANSEN TRUST

P.O. BOX 187

LOGAN, KS 67646

CONTR C-G DRILLING

#5 J. STORM

34-13-20W

SE SW NE

CTY ELLIS

GEOL JERRY JESPERSEN

FIELD PLEASANT

E 2253 KB CM 12/30/80 CARD ISSUED 6/11/81 IP P 10 80 & 90 BWPD

2248 GL ARB 3854-3868

API 15-051-22,182

+	+
+	+
+	+
+	+

LOG	TOPS	DEPTH	DATUM
ANH	1554	+ 699	
TOP	3231	- 978	
HEEB	3476	-1223	
TOR	3497	-1244	
LANS	3517	-1264	
BKC	3789	-1536	
MARM	3793	-1540	
CONG	3818	-1565	
ARB	3839	-1586	
TD	3840	-1587	

8 5/8" 207/175sx; 5 1/2" 3830/175sx

DST (1) 3508-3528/MISRUN
 DST (2) 3508-3528/15-45-60-45, REC
 976' G, 120' GO, 120' GOCM,
 SIP 1072-905#, FP 52-31/74-95#
 DST (3) 3588-3595/15-45-60-45, REC
 180' M, SIP 822-402#, FP 116-105/
 105-116#
 DST (4) 3612-3627/15-45-60-45, REC
 60' M, SIP 926-864#, FP 31-42/
 42-52#
 DST (5) 3638-3730/15-45-15-45, REC
 945' M, SIP 1468-1354#, FP
 391-466/423-529#
 MICT - CO, PF 3854-3868, NAT, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS