

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02050-00-00
Spot: SWNESW Sec/Twnshp/Rge: 11-10S-20W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: CROFFOOT Well #: 3
County: ROOKS Total Vertical Depth: 3855 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 603 MAIN AVE., STE 500
KNOXVILLE, TN 37902

L1 Size: 4.5 feet: 3450
PROD Size: 5.5 feet: 3780
SURF Size: 8.625 feet: 229

125²⁹

Well Type: OIL 6426 UIC Docket No: _____ Date/Time to Plug: 02/23/2005 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY Express Well Service per CP4 KC ap
Proposal Rcvd. from: _____ Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
5 1/2" set at 3780'. Drilled to 3855'. Set 4 1/2" liner from 3450' to 3855'.
PBTD 3845'. Fluid 375' from surface.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2005 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3500'.
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 200# hulls.
Pulled tubing to 2600'.
Allied pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1300'.
Allied pumped 60 sxs cement with 100# hulls - cement circulated.
PTOH. Squeezed with 30 sxs cement.
Max. P.S.I. 900#. S.I.P. 300#.
Hooked up to backside - instant pressure 500#.

Perfs:

Top	Bot	Thru	Comments
3798	3800		

RECEIVED
MAR 07 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 3.7.05

*INV. NO. 2005061250

MAR 01 2005

