

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20251-00-01
Spot: NWSWNW Sec/Twnshp/Rge: 12-17S-14W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WILLIAMS Well #: 1
County: BARTON Total Vertical Depth: 3505 feet

Operator License No.: 31428
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL
Address: PO BOX 417
VICTORIA, KS 67671

PROD Size: 5.5 feet: 3503 w/175 sxs cmt
SURF Size: 8.625 feet: 245 w/175 sxs cmt

113⁹¹

Well Type: EOR UIC Docket No: E17155.1 Date/Time to Plug: 03/18/2005 1:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: TED CRAWFORD Company: LONESTAR OIL COMPANY Phone: (785) 735-2725

Proposed Plugging Method: Ordered 290 sxs 60/40 pozmix - 10% gel with 1/4# flocele per sack and 500# hulls.
D.V. Tool at 450' to surface with 90 sxs.
Squeezed at 2529'-2556' with 150 sxs.
Low fluid level

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2005 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to backside at 8 5/8" and pressured with cement.
Max. P.S.I. 500#. S.I.P. 500#.
Rigged to 5 1/2" casing with a swedge.
Pumped 270 sxs with 500# hulls mixed in.
Max. P.S.I. 600#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3214	3456		

RECEIVED
MAR 23 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #14402.

Plugged through: CSG

District: 04

Signed 

(TECHNICIAN)

INVOICED

DATE

3-23-05

NO. 2005061317

Form CP-2/3

MAR 21 2005

WICHITA

MURFIN DRLG. CO. WICHITA, KS. #1 WILLIAMS APP 12-17-14W
 Contr. CO TOOLS ----- NW SW NW

Geol. ROBERT PATTON ----- Cty. BARTON
 Pool PUTNAM WEST

E. 1976 KB. Cm. 7/30/68 Cp. 12/5/68 IP PMP 25 BOPD/LANS
 API 15-009-20,251 3214-3456

LOG Tops	Depth	Datum
TOP	2894	- 918
HEEB	3130	-1154
TOR	3145	-1169
DOUG	3156	-1180
BR. CM	3202	-1226
LANS	3213	-1237
BKC	3418	-1442
CONG	3432	-1456
ARB	3452	-1476
LTD	3504	-1528
ADD TOP		
*ANH	932	+1044
SMP TOP		

Csg. 8" 245/175SX; 5 1/2" 3503 1/2/175
 DST 3206-50/90", 60' GIP, 60'
 SO&GCM, 120' HO&GCM, BHP 181-
 181#, FP 10-63#
 DST 3250-82/90", 180' GIP, 40'
 O&GCM, 60' HO&GCM, BHP 191-
 149#/30", FP 10-42#
 DST 3282-91/90", 50' WM, W/OIL SP
 BHP 575-575#/30", FP 10-21#
 DST 3332-3421/90", 120' GIP, 120'
 O&GCM, 540' HO&GCM, NW, BHP
 1002-872#/30", FP 121-319#
 PF 3452-56, 3432-37, 3403-09, 3380-
 85, 3364-68, 3348-51, 3274-77,
 3265-69, 3261-63, 3235-42, 3223-28,
 3214-20, A 4800

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS