

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: PO Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: ENHR Docket #: E-25,810
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 02-25-05 (Date)
by: Roger Moses (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
L/KC Depth to Top: 3530' Bottom: 3765' T.D. 3770'
____ Depth to Top: _____ Bottom: _____ T.D. _____
____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-20710-00-01
Lease Name: Griffith
Well Number: 2
Spot Location (QQQQ): ^{360S & 70'} W of SE - NE - NE *KCC BEM 3-25-05 RBDMS CP 2/3*
1040 Feet from North / South Section Line
400 Feet from East / West Section Line
Sec. 15 Twp. 10 S. R. 22 East West
County: Graham
Date Well Completed: 10/74
Plugging Commenced: 02-25-05
Plugging Completed: 02-25-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
L/KC	oil & water	3530'	3765'	8.625"	211'	0
				4.50"	3766'	0

RECEIVED
MAR 24 2005
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Top of parted stuck 2" plastic-lined-tubing at 1574'.
Ran 2" tubing to 1505'. Pumped 150 sx. 60/40 Pozmix cement w/ 10% Gel and 150# hulls down tubing.
Pulled tubing up to 925'. Pumped 65 sx. 60/40 Pozmix cement w/ 10% Gel down tubing; cement circ'd to surface. Pulled tbg.
Squeezed 4.50" csg w/ 10 sx. cement to 800#, shut in at 800#. Pumped 50 sx. cement w/ 150# hulls down 8.625" csg to 400#, shut in at 200#.

Name of Plugging Contractor: Allied Cementing Company Inc. Express Well Service License #: 6426
Address: PO Box 31 Russell, KS. 67665

KCC BEM 3-25-05 RBDMS CP 2/3

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of KS. County, Sedgwick, ss.

John C. Niemberger (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

JENNIFER L. FOSS
Notary Public - State of Kansas
My Appt. Expires 10/14/07

(Signature) [Signature]
(Address) PO Box 783188 Wichita, KS. 67278-3188

SUBSCRIBED and SWORN TO before me this 18th day of March 20 05
Jennifer L. Foss My Commission Expires: 10/14/07
Notary Public

[Handwritten mark]