

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Bear Petroleum Inc.

Address: PO Box 438, Haysville, KS 67120

Phone: (316) 524-1225 Operator License #: 4419

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: \_\_\_\_\_ (Date)

by: \_\_\_\_\_ (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: <sup>159</sup> ~~15-N/A~~ - 30257-00-00

Lease Name: Steierl

Well Number: 1

Spot Location (QQQQ): \_\_\_\_\_ - SW - SW - NE

2970 Feet from  North /  South Section Line

2310 Feet from  East /  West Section Line

Sec. 27 Twp. 21 S. R. 7  East  West

County: Rice

Date Well Completed: \_\_\_\_\_

Plugging Commenced: 03-14-05

Plugging Completed: 03-16-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	219	
				5 1/2	3472	1320'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3341', bailed 5 sacks of Portland, ripped 1320', worked free, pulled to 1000', pumped 35 sacks, pulled to 550', pumped 35 sacks, pulled to 270', pumped 12 gel and 135 sacks of cement, pulled rest of pipe.

RECEIVED

MAR 23 2005

KCC WICHITA

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 401 West Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: Bear Petroleum Inc.

State of Kansas County, Sedgwick, ss.

R.A. Schremmer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) P.O. Box 438, Haysville, KS 67060

SUBSCRIBED and SWORN TO before me this 22nd day of March, 2005

Shannon Howland My Commission Expires: 3/10/08  
Notary Public

SHANNON HOWLAND  
Notary Public - State of Kansas  
My Appt. Expires 3/10/08

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Bear*

# Quality Well Service, Inc.

401 West Main  
Lyons, KS 67554

# Invoice

Date	Invoice #
03/21/2005	645

Bill To
Bear Petroleum, Inc. PO Box 438 Haysville KS 67060

P.O. No.	Terms	Lease Name
	net	Steierl #1

Description	Qty	Rate	Amount
Rig Time	22.5	135.00	3,037.50T
Trucking Floor	1	90.00	90.00T
Sand	1	35.00	35.00T
Cement	5	9.00	45.00T
Ripping Pipe	1	140.00	140.00T
Water Truck	5	60.00	300.00T
Backhoe	5	65.00	325.00T
Phone Calls	1	10.00	10.00T
Clerical	1	10.00	10.00T
Wiping Rubber	1	15.00	15.00T
Fresh Water	1	10.00	10.00T
03-14-05 Rigged up tore flow tee down pulled part of rods went in.			
03-15-05 Pulled rest of rods, unset packer, pulled tubing, sanded bottom, loaded hole, dug cellar and pit, tore head down, set floor, pulled slips, checked hole, sand at 3341', bailed 5 sacks of Portland, pulled stretched pipe, parted, put back together, cut casing head off, went in.			
03-16-05 Ripped 1320', worked free, pulled to 1000', pumped 35 sacks, pulled to 550', pumped 35 sacks, pulled to 270', pumped 12 gel and 135 sacks of cement, pulled rest of pipe, washed pipe, out filled cellar, sucked pit out, filled it in, tore down, loaded out.			
<b>Subtotal</b>			\$4,017.50
<b>Sales Tax (6.3%)</b>			\$253.10
<b>Total</b>			\$4,270.60

RECEIVED  
MAR 23 2005  
KCC WICHITA