

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.  
Address: 250 N. Water, Suite 300  
Phone: (316) 267-3241 Operator License #: 30606  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 2/2/05 (Date)  
by: Rich Williams w/ KCC in Hays, KS (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
3266-3270 Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
3004-3010 Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
2842-2850 Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 051-21,899 - 00 - 01  
Lease Name: Hadley D  
Well Number: 18  
Spot Location (QQQQ): S2 - \_\_\_\_\_ - \_\_\_\_\_  
1380 Feet from  North /  South Section Line  
2640 Feet from  East /  West Section Line  
Sec. 17 Twp. 11 S. R. 17  East  West  
County: Ellis  
Date Well Completed: 3/4/80 original well  
Plugging Commenced: 3/7/05  
Plugging Completed: 3/8/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	248.6	8 5/8	248.6	0
	Production	Surface	3479	5 1/2	3479	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


3/7/05: Ran 2 3/8" to 2790'. Allied set up to plug, pressured annulus to 500 psi, spot 175 sx 60/40 Poz, 10% gel, & 600# hulls @ 2790', pull tbg to 1400', spot 125 sx, 200# hulls, pull tbg to 700', spot 75 sx, no circ or blow on annulus, pull tbg, SDON. Finish on 3/8/05.

3/8/05: Run tbg swab, tag cement @ 1300', TIH W/2 3/8" TO 1085', Allied set up to plug, mixed 80 sx 60/40 Poz, 10% gel, circ cmt to surface.

TOH w/ 2 3/8", hookup to 5 1/2", mixed 10 sx, squeeze to 500 psi, SI. Witnessed by Rich Williams/KCC. Job complete 10:30 am.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606  
Address: 250 N. Water, Suite 300 ; Wichita, KS 67202  
Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.  
State of Kansas County, Sedgwick, ss.  
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED  
MAR 24 2005  
KCC WICHITA



(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202

and SWORN TO before me this 23rd day of March, 20 05

Susan Brady My Commission Expires: 11-4-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202