

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: _____ (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
3606-3610.5 Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-05981-00-00

Lease Name: Glathart

Well Number: #3

Spot Location (QQQQ): S2 - SW - SE -
330 Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec. 29 Twp. 11 S. R. 17 East West

County: Ellis

Date Well Completed: _____

Plugging Commenced: 2/25/05

Plugging Completed: 2/25/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	1250	8 5/8	1250	0
	Production	Surface	3651	4 1/2	3651	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 3/8" open ended tbg to 2790'. Allied set up to plug. Spot 120 sx 60/40 Poz, 10% gel @ 2790', pulled tbg to 1300', spot 265 sx, cement circ out 4 1/2" and 8 5/8" TOH with 2 3/8" tbg, hookup to 4 1/2" pumped 15 sx, pressured to 500# shut in @ 300#.

Witnessed by Rich Williams w/KCC. Job complete at 6:00 pm 2/25/05.

RECEIVED

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

MAR 24 2005

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.


KCC WICHITA

State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 22nd day of March, 2005

Susan Brady My Commission Expires: 11-4-07
Notary Public