

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

K.A.R. 82-3-117
RECEIVED

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188 Wichita KS. 67278-3188
Phone: (316) 691-9500 Operator License #: 4767

API Number: 15-109-20706-00-01

Lease Name: Becker 35D

Well Number: #1

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): 120°E of - S/2 - SE -

660' Feet from North / South Section Line

1200' Feet from East / West Section Line

Sec. 35 Twp. 12 S. R. 35 East West

The plugging proposal was approved on: 08-03-2004 (Date)

County: Logan

by: David Williams (KCC District Agent's Name)

Date Well Completed: 9/23/03

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Plugging Commenced: 11/09/04

Producing Formation(s): List All (If needed attach another sheet)

Altamont Depth to Top: 4292' Bottom: 4297' T.D. _____

Johnson Depth to Top: 4526' Bottom: 4529' T.D. _____

Plugging Completed: 11/09/04

_____ Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|-----------|--|-------|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| L/KC | oil/water | 3898' | 4212' | 8.625" | 325' | 0 |
| Altamont | oil/water | 4281' | 4337' | 4.50" | 4646' | 0 |
| Johnson | oil/water | 4476' | 4536' | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed and pumped 215 sx. 60/40 Pozmix cement w/ 10% Gel and 500# hulls, down 4 1/2" casing. Maximum pressure = 750#.

Shut in at 500#, held.

Pressured 8 5/8" casing to 500#, held; no additional cementing necessary.

Plugging complete at 10:40 AM on 11-09-04, witnessed and approved by Darrell Dippman w/ the KCC.

Name of Plugging Contractor: Allied Cementing Company Inc. License #: 99996


Address: PO Box 31 Russell, KS. 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.

State of Kansas County, Sedgwick, ss.

John Niernberger

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) _____

(Address) PO Box 783188 Wichita KS. 67278-3188

SUBSCRIBED and SWORN TO before me this 23rd day of March, 20 05

Notary Public My Commission Expires: 10-14-07

ALLIED CEMENTING CO., INC. 19742 ✓

Federal Tax I.D.# [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
DAKLEY

| | | | | | | | |
|--|-------------------|--------------------|--|------------|-------------------------------|-----------------------------|-------------------------------|
| DATE <u>11-9-04</u> | SEC. <u>35</u> | TWP. <u>12S</u> | RANGE <u>35W</u> | CALLED OUT | ON LOCATION <u>9:13 AM</u> | JOB START <u>9:45 AM</u> | JOB FINISH <u>10:30 AM</u> |
| LEASE <u>BECKER 35-0</u> | | WELL # <u>1</u> | LOCATION <u>RUSSELL SPRINGS 3N-1/2E-NE106AN</u> | | | COUNTY | STATE <u>Ks</u> |
| <input checked="" type="radio"/> OLD OR NEW (Circle one) | | | | | | | |

CONTRACTOR NONE
 TYPE OF JOB OLD HOLE
 HOLE SIZE _____ T.D. _____
 CASING SIZE 4 1/2" DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER SAME
 CEMENT
 AMOUNT ORDERED 275 SKS 60/40 POZ 10% GEL
500# HULLS
USED 215 SKS 60/40 POZ 10% GEL 500# HULLS
 COMMON 129 SKS @ 9.10 1173.90
 POZMIX 86 SKS @ 4.00 343.60
 GEL 18 SKS @ 11.00 198.00
 CHLORIDE _____ @ _____
 ASC _____ @ _____

EQUIPMENT

PUMP TRUCK CEMENTER TERRY
 # 191 HELPER FUZZY
 BULK TRUCK _____
 # 218 DRIVER JARROD
 BULK TRUCK _____
 # _____ DRIVER _____

HULLS 500# @ 20% 100%
 HANDLING 303 SKS @ 1.35 409.05
 MILEAGE 0.54 PER SK / MILE 409.05
 TOTAL 2642.60

REMARKS:

HOOK ON TO 4 1/2 CASING 6 MEX
215 SKS CEMENT WITH 500# HULLS
MAX PRESSURE 750 PSI SHUT IN
AT 500 PSI HOOK ON BACKSIDE
PRESSURE TO 500 PSI, NO CEMENT.

THANK YOU

CHARGE TO: RITCHIE EXPLORATION, INC
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE
 DEPTH OF JOB _____
 PUMP TRUCK CHARGE 525.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 27 MI @ 4.00 108.00
 MANIFOLD _____ @ _____
 TOTAL 633.00

PLUG & FLOAT EQUIPMENT

 @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 TOTAL _____

NO CO. MAN ON LOC.

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE _____

PRINTED NAME _____

RECEIVED
 MAR 24 2005
 KCC WICHITA



March 23rd, 2005

State Corporation Commission
Conservation Division
130 S. Market, Room 2078
Wichita, KS 67202

RE: **Well Plugging Record (CP-4)**
#1 Becker 35D
120' E of S/2 SE
Sec. 35-12S-35W
Logan County, Kansas

RECEIVED
MAR 24 2005
KCC WICHITA

To Whom It May Concern:

Enclosed please find the Well Plugging Record (CP-4) for the above referenced well.

If you have any questions, please feel free to call the undersigned or John Niernberger at 316-691-9500. Thank you for your assistance in this matter.

Sincerely,

A handwritten signature in cursive script, appearing to read "Jennifer Foss".

Jennifer Foss
Production Assistant

jlf

Enclosures