

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20540-00-00
RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1974
09-13-1974
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: Zenith Drilling Corporation,

Complete Address: Suite 600, 200 W. Douglas, Wichita, Kansas.

Lease Name: Hamit Well No. 1

Location: NE-SE-SE Sec. 20 Twp. 6 Rge. (E)(W) 19

County: Rooks Total Depth 3612' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Niernberger was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

N. L. Pihel
Conservation Division Agent