



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1972
08-17-1972
CONSERVATION DIVISION
Wichita, Kansas

15-163-20454-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Buchheister of John O. Farmer Drlg. has this

date requested permission to plug the following described well:

Mr. Buchheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.

Complete Address: 370 W. Wichita Ave. Russell, Kansas 67665

Lease Name: Brobst Well No. 2

Location: C SE SW Sec. 8 Twp. 6 Rge. (E)(W) 19

County: Rooks Total Depth 3695' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Buchheister was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Bea J. Massey
Conservation Division Agent