

# WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

## FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Rooks County, Sec. 32, Twp. 6, Rge. (E) ~~19~~ (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C S $\frac{1}{2}$  SW $\frac{1}{2}$  SW $\frac{1}{2}$

Lease Owner Helmerich & Payne, Inc. et al

Lease Name Liebenau Well No. 1

Office Address Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed June 6, 19 41

Application for plugging filed (Verbal) June 7, 19 41

Application for plugging approved (Verbal) June 7, 19 41

Plugging Commenced June 7, 19 41

Plugging Completed June 7, 19 41

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation None Depth to top Bottom Total Depth of Well 3566 Feet

Show depth and thickness of all water, oil and gas formations.


### OIL, GAS OR WATER RECORDS

### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	152	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran drill pipe to bottom. Circulated heavy mud at 500 ft. intervals from bottom to 152 ft. Hole bridged at 152 ft. in bottom of surface casing with wood plug, rock and burlap. Dumped cement to form plug from 152 to 132. Filled with heavy mud to 18 feet below top of surface casing. Filled to top with cement.



06-18-1941

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Helmerich & Payne, Inc.  
Address 415 Philtower Building, Tulsa, Oklahoma.

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.  
\_\_\_\_\_ (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C M Copeland*

415 Philtower - Tulsa Okla  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of June, 19 41

My commission expires July 27, 1943

*Joe Luffman*  
Notary Public.