

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER 15-163-22,973 00-00

LEASE NAME Ostmeyer

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 31 TWP. 6 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 12-31-87

Plugging Commenced 12-31-87

Plugging Completed 12-31-87

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 125 N. Market Suite 1110 Wichita, Ks. 67202

PHONE#(316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District 6 Hays, Ks. Ed Schumacker State Plugger

Is ACO-1 filled? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	260	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

1st plug from 3555 to 3475 with 20sx; Pump mud to 1625. 2nd plug from 1625 to 1545 with 20sx; Pump mud to 955. 3rd plug from 955 with 100sx; Pump mud to 310'; 4th plug from 310' to 150' with 40sx; Pump mud to 40' wiper plug & 10sx from 40' to surface. 15sx in rat hole. All cement 60/40 posmix with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie, Drilling, Inc. License No. 5422

Address 801 Union Center Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack K. Wharton

(Address) 801 Union Center
Wichita, KS 67202

7th day of January, 1988

Janet A. Stuck
Notary Public

Commission Expires: 12-29-90



RECEIVED
 STATE CORPORATION COMMISSION
 08 1988
 01-08-1988
 CONSERVATION DIVISION
 Wichita, Kansas