

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-065-21,329-00 ⁰¹~~21~~

LEASE NAME Lagerberg

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 11 TWP. 6 RGE. 21 (S) or (W)

COUNTY Graham

Date Well Completed March 1981

Plugging Commenced Aug. 28, 1992

Plugging Completed Aug. 28, 1992

LEASE OPERATOR Petroleum Management Inc.

ADDRESS 14201 E. Central Wichita, KS 67230

PHONE# (316) 733-5600 OPERATORS LICENSE NO. 5242

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 28, 1992 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3923

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
KC		3474	3661	8 5/8	223	0
Marmaton		3700	3706	4 1/2	3818	0
Conglomerate		3706	3754			
Arb		3754				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Ran tubing to 3656'. Spotted 75 sx 60-40 Poz 8% Gel 1/4# Flo Seal. Pulled to 2250'.
Spotted 75 sx 200# Halls. Pulled to 850'. Spotted 25 sx cement. Circulated. Pumped 25 sx
down 4 1/2. Max PSI 1000#. Shut in at 1000#. Pressure 8 5/8" to 1000#. Held.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management Inc. ^{RECEIVED} STATE CORPORATION COMMISSION License No. 5242

Address 102 N. Washington Plainville, KS 67663 ^{NOV 24 1993}

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management Inc.

STATE OF Kansas COUNTY OF Sedgewick ^{Wichita, Kansas} _{Conservation Division}, ss.

Steven P. O'Neill (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Donald H. Keenan

14201 E. Central, Wichita, KS 67230 (Address) 204 N. Plainville, KS 67663

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 19 93

Kathleen L. Carter Notary Public

My Commission Expires: _____
 NOTARY PUBLIC
 STATE OF KANSAS

EXPIRES 4-29-95