

2-3 4-061043

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-23,294-00-00

NW SE NW /4 SEC. 33, 06 S, 19 W  
3630 feet from S section line  
3630 feet from E section line

Operator license# 5290

Lease Griebel Well # 1

Operator: Hinkle Oil Company

County: Rooks 117.00

Address: 150 N. Main - Suite #1016  
Wichita, Kansas 67202

Well total depth 3600 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 312 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Duke Drilling Company, Inc. License# 5929

Address: Wichita, Kansas 67202

Company to plug at: Hour: 5:00 P.M. Day: 3 Month: February Year: 1997

Plugging proposal received from: Galen Boach

Company: Duke Drilling Company, Inc. Phone:

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED  
KANSAS CORP COM  
1997 FEB 12 P 2:58  
02-12-1997

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 8:00 P.M., Day: 3, Month: February, Year: 1997

Actual plugging report:

- 1st. Plug at 1660' w/25 sxs. Anhydrite 1646' - 1673'.
- 2nd. Plug at 975' w/100 sxs. Dakota 674' - 974'.
- 3rd. Plug at 375' w/40 sxs. Surface pipe at 312'.
- 4th. Plug at 40' w/10 sxs.
- 15 sxs in rathole.
- 10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: 2074 GL

I did not [ X ] observe the plugging.

INVOICED

DATE FEB 14 1997

INV. NO. 47573

(agent)  
Form CP-2/3

2-3