

4-041537

8-28
15-065-21329-00-22

D-25,183

API number: 15- -

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW SE /4 SEC. 11, 06 S, 21 W
1650 feet from S section line
1650 feet from E section line

Operator license# 5242 Lease Lagerberg well # 1

Operator: Petroleum Management, Inc. County Graham

Address: P.O. Box H Well total depth 3923 feet ^{127.49}
Plainville, Kansas 67663 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 218 feet
w/100 sx.

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 28 Month: August Year: 92

Plugging proposal received from: Don Keener

Company: Petroleum Management, Inc. Phone:

Were: 4 1/2" casing set @ 3818' w/185 sx. cement. O.H. @ 3818' -
3923'. D.V. @ anhy. @ 1860'. Ordered 300 sx. 60/40 pozmix - 8% gel -
1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:45P.M. Day: 28 , Month: August , Year: 92

Actual plugging report: R.I.H. with tubing to 3650'. Spot 75 sx. cement
pulled to 2200' - spot 75 sx. cement. Pulled tubing to 850' - spot
25 sx. cement to circulate at surface. Pulled tubing and squeezed
casing with 25 additional sx. cement. Max. 1000#. S.I.P. 1000#.
Pressured-up 8 5/8" to 1000#.

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1993

CONSERVATION DIVISION
Wichita, Kansas

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X , CALC , NO Dakota plug: YES X , NO
Plugged through TUBING X , CASING . Elevation: GL

I did X observe the plugging.

Dennis L. Hamel
(agent)

HD

Form CP-2/3

INVOICED

DATE NOV 17 1993

INV. NO. 39216