

5-31-88

065-22,457 -00-00

6 070686

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
SE SW SE, SEC. 23, T 6 S, R 21 W/E

330 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Hansen Foundation Well # 1

Operator: Ritchie Exploration, Inc.  
Name & Address: 125 N. Market, #1000  
Wichita, Kansas 67202  
Jeff Christian

County Graham  
Well Total Depth 3780 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 217

122.85

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 4767 Tag #604

Address Wichita, Kansas 67202

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Lloyd Delleste

(company name) Murfin Drilling Co. (phone) 316-267-4375

were: 8 5/8" - 217' SP cir. w/ 180 sx 60/40 pozmix, 3% gel, 2% cc - by Allied Cmt. Co.

Arbuckle @ 3760', Elv. 2235', Anhydrite @ 1842' mud cond. 9.5 wt, 45 vis. 10.4 water loss.

No circulation problems. Proposal 215 sx 60/40 pozmix, 6% gel, 3% cc, 1sck celloflake, and

8 5/8" plug. Spot with drill stem, circulate, mud between all plugs. 25 sx @ 3690', 25 sx

@ 1860', 100 sx @ 1140', 40 sx @ 270', 10 sx @ 40', 15 sx in rat hole and circulate.

Plugging Proposal Received by Marion Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXX

Operations Completed: Hour: 9:30 pm Day: 31 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Ordered 215 sx 60/40 pozmix, 6% gel, 3% cc, 1 sx flocele, and 8 5/8"

plug. Spotted with drill stem, circulated with mud between all plugs.

1st Plug @ 3690' w/25 sx cmt 5th Plug @ 40' w/10 sx cmt & hulls.

2nd Plug @ 1860' w/25 sx cmt 15 sx rat hole (circulated)

3rd Plug @ 1140' w/100 sx cmt and 1 sck flocele Cemented by Allied Cmt Co.

4th Plug @ 270' w/40 sx cmt

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging. 5 1988

DATE 7-8-88

INV. NO. 21242

CONSERVATION DIVISION  
Wichita, Kansas

Signed Marion Schmidt (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 5/17/88 month day year

API Number 15-065-22,457-00-00

OPERATOR: License # 4767
Name Ritchie Exploration, Inc.
Address 125 N. Market, Suite 1000
City/State/Zip Wichita, KS 67202
Contact Person Jeff Christian
Phone 316/267-4375

SE SW SE Sec. 23 Twp. 6 S, Rg. 21
330 Ft. from South Line of Section
1650 Ft. from East Line of Section

CONTRACTOR: License # 6033
Name Murfin Drilling Co.
City/State Wichita, KS 67202

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County Graham

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Lease Name Hansen Foundation Well # 1
Ground surface elevation 2230 feet MSL
Domestic well within 330 feet: yes X no

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Municipal well within one mile: yes X no
Depth to bottom of fresh water 100
Depth to bottom of usable water 1200
Surface pipe by Alternate: 1 2 X

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 5/10/88 Signature of Operator or Agent Jeff Christian Title Geologist

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2
This Authorization Expires 11-10-88 Approved By PH 5-10-88

EFFECTIVE DATE: 5-15-88

Spud 5-25-88
Loyd Delett
SP. 200'-216'

HAZARDING WATER -

SE SW SE Sec. 23 Twp. 6 S, Rg. 21 X East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, formation, cement sacks, and mousehole/rathole details.

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging. In Addition: Call district office before well is either plugged or production casing is cemented in. (Call 7 a.m. to 5 p.m. workdays)

District office use only:

API #15-065-22,457
Surface casing of feet set with... sxs at... hours...
Alternate 1 or 2 surface pipe was used...
Alternate 2 cementing was completed @ ft. depth with... sxs on...
Hole plugged... agent... Received KCC District #6

Conservation Division
Wichita, Kansas

MAY 11 1988

Hays, KS