

4-050325

2-18

TO:

API Number: 15-039-00587-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW NE SE /4 SEC. 34, 06 S, 27 W
1650 feet from S section line
990 feet from E section line

Operator license# 32334

Lease: N.W. Adell Well # 15

Operator: Chesapeake Operating, Inc.

County: Decatur 122.69

Address: 6200 N. Western Avenue
P.O. Box 18496
Oklahoma City, OK 73154
(405) 848-8000

Well total depth 3775 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 236 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Murfin Drilling License# -

Address:

Company to plug at: Hour: A.M. Day: 18 Month: February Year: 1999

Plugging proposal received from: Jeff Wood

Company: Phone:

Were: 10 3/4" surface casing set at 236' with 200 sxs.
7" production casing set at 3762' with 200 sxs.
Perforations at 3793' - 3796', 3650' - 3724'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 5:00 P.M. Day: 18 Month: February Year: 1999

Actual plugging report: 01/27/98 - Tied onto 7" casing - pumped 50 sxs 60/40 pozmix - 10% gel 200# hulls, followed with 20 sxs gel and 500# hulls. Perforated at 1450' and 2260'. Pumped 225 sxs cement down casing. Tied onto backside - pumped and squeezed with 100 sxs cement - pressured to 200# - Held. Set 3 hours - tied onto casing. Pumped 150 sxs cement. Well on vaccum. 02-04-99 - Ran wireline top of cement at 1440' - filled casing with fresh water and pressured to 100# - Held. 02-15 to 18-99 - Drilled hole out to 3467' and tied onto 7" casing. Pumped 150 sxs common cement with 2% c.c. Followed with 150 sxs 60/40 pozmix - 10% gel and 1000# hulls. Set CIBP at 3350' - tied onto casing. Pumped and squeezed with 430 sxs cement and 1200# hulls. Max. P.S.I. 500#. S.I.P. 400#.

Remarks:
Condition of casing (in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug (in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: 2858 GL

I did [X] / did not [] observe the plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Martin Miller (agent)

DATE 4-8-99

APR 7 1999

Form CP-2/3

INV. NO. 60802

CONSERVATION DIVISION Wichita Kansas

2-18