

6 070143

API NUMBER 15-065-21.977 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW NE, SEC. 25, T 6 S, R 21 W

990 feet from N/S section line

1650 feet from W/E section line

Lease Name Lytle Well # 1

County Graham

Well Total Depth 3732 121.29 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 365

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Operator: Frontier Oil Co.

Name & Address 1720 Kansas State Bank Bldg.

Wichita, Ks. 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number 5302 Tag #81

Address 1720 K.S. Bank Bldg., Wichita, Ks. 67202

Company to plug at: Hour: 11 AM Day: 5th Month: May Year: 19 84

Plugging proposal received from Bill Ayers

(company name) Red Tiger Drilling Company (phone) (316) 263-1201

were: 8 5/8" 365' SP CUC w/200 sks common 2% gel 3% cal. cl. (By Allied Cmt.)

Ordered 220 sks 50/50 pozmix 6% gel 3% cal. cl.- 1 sk cello flake and 8 5/8" Plug

spot with drill stem, turn hole over, heavy mud between all plugs No circulation

problems, Arbuckle @ 3716 - Elevation 2235' Anhy 1842.

Plugging Proposal Received by Maryann Schmidt
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15 AM Day: 5th Month: May Year: 19 84

ACTUAL PLUGGING REPORT Ordered 220 sks 50/50 pozmix 6% gel 3% cal. cl.- 1 sk cello-flake and 8 5/8" plug spotted with drill stem - turned hole over - heavy mud between all plugs.

1st plug @ 3660' w/25 sks cmt (Cemented by Allied Cmt.)

2nd plug @ 1860' w/25 sks cmt

3rd plug @ 1120' w/100 sks cmt. w/1 sk cello-flake

4th plug @ 370' w/50 sks cmt

5th plug solid bridge hulls & Plug @ 40' to 0 w/10 sks cmt.-10 sks in Rat Hole

Remarks: if additional description is necessary, use BACK of this form.)

INVOICED

I (did/did not) observe this plugging.

DATE 5-18-84

Signed Maryann Schmidt
DOIC (TECHNICIAN)

INV. NO. 1543

MAY 23 1984