

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 065-21, 923 -00-00

NW-NW-NE, Sec. 23, T 6 S, R 21 (W)E

330 feet from (N)S section line

2310 feet from (W)E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Lease Name GRIFFIN Well # 1

Operator: PETROLEUM MANAGEMENT,  
Name & INC.  
Address 400 N. WOODLAWN #301  
WICHITA, KANS.  
316-~~848~~ 67208  
6867287

County GRAHAM

Well Total Depth 3850 feet 125.12

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 376

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor RED TIGER DRILLING License Number 5302

Address 1720 K.S.B+T BLDG., WICHITA, KANS. 67202

Company to plug at: Hour: 1:00 PM Day: 15<sup>th</sup> Month: JAN Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO TEN LYLE

(company name) RED TIGER DRILLING (phone) 316-263-2371

were:

8 5/8" - 376<sup>5</sup> SP. CUL #300 <sup>SK 60</sup> /40 FORMIX GEL - CA-CL. 2% 3% BY HALLIBURTON.  
ORDER 210 <sup>SK 50</sup> /50 FORMIX 6% GEL - 3% CA-CL. - 2<sup>SK CULO</sup> FLANGE AND 8 5/8" PLUG  
NO SHOW OR BLOW - NO CIRCULATION PROBLEMS, ELV. 2277, ANH 1916  
ARBUCKLE - 3796.

Signed Marion Schmidt  
(TECHNICIAN) 8016

Plugging Operations attended by Agent?: All  Part  None X

Operations Completed: Hour: 5:00 PM Day: 15<sup>th</sup> Month: JAN Year: 1984

ACTUAL PLUGGING REPORT

ORDERED - 210 <sup>SK 50</sup> /50 FORMIX GEL - CA-CL., 2<sup>SK CULO</sup> FLANGE, AND 8 5/8" PLUG.  
SPOTTED WITH DRILL STEM, TURNED HOLE OVER, HEAVY MUD BETWEEN ALL PLUG.  
1<sup>st</sup> PLUG @ 3780 <sup>FI #</sup> /20 <sup>SK</sup> CMT. - 2<sup>nd</sup> PLUG @ 1920 <sup>FI #</sup> /20 <sup>SK</sup> CMT.  
3<sup>rd</sup> PLUG 1170 <sup>FI #</sup> /100 <sup>SK</sup> CMT. - 4<sup>th</sup> PLUG @ 390 <sup>FI #</sup> /50 <sup>SK</sup> CMT.  
5<sup>th</sup> PLUG <sup>SOLID BRIDGE</sup> HUNS. PLUG @ 40 <sup>FI #</sup> /10 <sup>SK</sup> CMT., 10 <sup>SK</sup> RAT HOLE (CIRCULATE)

Remarks: CEMENTED BY ALLIED CMT.

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ / did not observe this plugging.

Signed Marion Schmidt  
(TECHNICIAN) 8016

INVOICED RECEIVED  
STATE CORPORATION COMMISSION

DATE 1-27-84 JAN 23 1984 1-23-84

INV. NO. 9273  
CONSERVATION DIVISION  
Wichita, Kansas