

4-032114

11-29

API Number: 15-065-22,525-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NW NW NE /4 SEC. 18, 06, 21 W
4900 feet from S section line
2310 feet from E section line

Operator license# 4767

Lease: David Frazey Well # 1

Operator: Ritchie Exploration, Inc.

County: Graham

Address: 125 N. Market - #1000
Wichita, Kansas 67202

Well total depth 3846 ^{125.00} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 266 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 29 Month: November Year: 1995

Plugging proposal received from: John Niernberger

Company: Ritchie Exploration, Inc. Phone: _____

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1995

12-13-95
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 9:30 A.M., Day: 29, Month: November, Year: 1995

Actual plugging report: 8 5/8" set at 266' cwc with 180 sxs. 4 1/2" set at 3829' with 125sxs. Prod. Perfs 3478' - 3631'. P.B.T.D. at 3778'. Port collar set at 1976' with 550 sxs cwc. Squeezed 4 1/2" with 300 sxs cement blend with 500# hulls to Max. P.S.I. 900#. Close in P.S.I. 200#. Plug complete.

Remarks: Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did did not observe the plugging.

Carl Goodrow
(agent)

Form CP-2/3

DATE 12-13-95

INV. NO. 44347

MD.