

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21,737-00008

SW, Sec. 22, T 6 S, R 21 W/E
330 feet from N/S section line
330 feet from W/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5005

Lease Name Pennington Well # 1

Operator: Sun Burst Exploration
Name & Address 708 One Place, Wichita, Ks.
67202

County Graham

Well Total Depth 3910 feet 127.08

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 284

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Oily, Inc. License Number 179

Address 801 Union Sta. Wichita, Ks. 67202

Company to plug at: Hour: 7:00 AM Day: 13 Month: 2 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Harold Maloy

(company name) Abercrombie Oily, Inc. (phone) 316-262-1841

were: Order 180 shs. 50% pos mix - 4% gel - 3% lb. U. & 8 5/8" plug.

Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3900' w/ 20 shs. 2nd plug C 1974' w/ 20 shs. 3rd plug C 1160' w/ 80 shs. 4th plug C 300' w/ 40 shs. 5th plug - solid bridge of bulls & plug. C 40' w/ 10 shs. Circulate 10 shs in rat hole & 10 shs in mouse hole

Signed G. J. Schiefel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:00 AM Day: 13 Month: 2 Year: 19 83

ACTUAL PLUGGING REPORT 8 5/8" - 284' SP. conc. w/ 200 shs. common - 2% gel - 3% lb. U.

Order 180 shs. 50% pos mix - 4% gel - 3% lb. U. + 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3900' w/ 20 shs. 2nd plug C 1974' w/ 20 shs. 3rd plug C 1160' w/ 80 shs. 4th plug C 300' w/ 40 shs. 5th plug - solid bridge of bulls & plug C 40' w/ 10 shs. Circulated 10 shs in rat hole & 10 shs in mouse hole.

Remarks: Drilled in Arbuckle.

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1983

CONSERVATION DIVISION
Wichita, Kansas 3-14-83

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed G. J. Schiefel
(TECHNICIAN)

INVOICED

DATE MAR 28 1983

INV. NO. 3788W

FORM CP-2/3
Rev. 9-82