

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21,930 -00-00

SW SW SE, Sec. 19, T 6 S, R 21 W/E
330 feet from N/S section line
2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Bozarth Well # 1

Operator: A. Scott Ritchie
Name & Suite 950
Address 125 N. Marker
Wichita, Kansas 67202

County Graham

Well Total Depth 3885 feet 126.26

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 239

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number

Address 250 N. Water, Suite 300, Wichita, Kansas 67202

Company to plug at: Hour: 4 AM Day: 10 Month: February Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Bernie Meyer

(company name) Murfin Drilling Company (phone)

were: Order 210 sks. 50/50 poz mix 6% gel 3% cc @ 1-8 5/8" plug Jett Pitts circualte hole
with heavy mud and displace 20 sks. cement thru drill pipe at 3825' - heavy mud to 1945' and
displace 20 sks: cement thru drill pipe, heavy mud to 1160' and displace 100 sks cement
thru drill pipe - heavy mud to 250' and 40 sks cement - heavy mud to 40' set 8 5/8 plug.
1/2 sk hulls and 10 sks cement - cementing to base of cellar. 10 sks in rat hole and 10 sks
in fresh water well

Signed Gilbert P. Lerker
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:45 AM Day: 10 Month: February Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 3825 w/20 sks. 10 sks in fresh water well

2nd plug @ 1945 w/20 sks.

3rd plug @ 1160 w/100 sks.

4th plug @ 250 w/40 sks.

5th plug @ 40 w/8 5/8 plug 1/2 sk hulls and 10 sks cement

10 sks. in Rat Hole

RECEIVED
STATE CORPORATION COMMISSION

Remarks:

FEB 21 1984

CONSERVATION DIVISION
Wichita, Kansas

2-21-84

I hereby certify that the above plugging instructions were given as herein stated
and that I (did did not) observe this plugging.

Signed Gilbert P. Lerker
(TECHNICIAN)

INVOICED

DATE 2-23-84

INV. NO. 0354

2-10