

6 070150

API NUMBER 15- 065-21,975 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N¹/₂ NW SW, SEC. 18, T. 6 S, R. 21 W/EX

2310 feet from XX section line

660 feet from W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Worcester Trust Well # 1

Operator: A. Scott Ritchie

County Graham

Name & Address 125 North Market Suite 950

Well Total Depth 3902 126.82 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 259

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033 Tag # 604

Address 250 North Water, Wichita, Ks. 67202

Company to plug at: Hour: 2 PM Day: 16 Month: May Year: 19 84

Plugging proposal received from Lloyd Dellett

(company name) Murfin Drilling Company (phone) (316) 267-4375

were: 8⁵/₈" 259' SP CUC w/175 sks common 2% gel 3% cal. cl. by Allied Cementing Company

Order 220 sks 50/50 pozmix 6% gel 3% cal. cl. 1 sk cello flake and 8⁵/₈" plug. Spot with

drill stem, turn hole over, heavy mud between all plugs. No circulation problems.

Elevation 2332' Anhy 1981' Arbuckle 3875'

Plugging Proposal Received by [Signature]
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7 PM Day: 16 Month: May Year: 19 84

ACTUAL PLUGGING REPORT Cemented by: ALLIED CMT

1st plug @ 3840' w/25 sks cmt

2nd plug @ 2010' w/25 sks cmt

3rd plug @ 1230' w/100 sks cmt and w/1 sk cello-flake

4th plug @ 270' w/50 sks cmt

5th plug solid bridge hulls plug @ 40' w/10 sks cmt.

10 sks in Rat Hole (Circulate)

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

DATE 5-22-84

Signed [Signature]
DOIC (TECHNICIAN)

INV. NO. 1624 5-16 JUN 04 1984

RECEIVED
STATE CORPORATION COMMISSION
5-21-84
MAY 21 1984
CONSERVATION DIVISION
Wichita, Kansas