

6010157

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22,001-00-00

SE/4, SEC. 16, T. 6 S, R. 21 W/2
2970 feet from N/E section line

330 feet from #1/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Lease Name: Voss Well # "B"-1

Operator: Petroleum Mgmt. Inc.

County Graham

Name & Address 400 N. Woodland

Well Total Depth 3888 126.36 feet

Suite 201

Conductor Pipe: Size _____ feet

Wichita Ks.

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drlg. Co. License Number 5302

Address 1320 Ks. St. Bldg. Wichita Ks.

Company to plug at: Hour: PM Day: 30 Month: 6 Year: 19 84

Plugging proposal received from Mike Wagoner

(company name) Red Tiger Drlg. Co. (phone) 913-625-7966

were: order 210 sx. cement 50/50 poznix 6% gel. 3% cal. cl.

1 sx hulls 1- 8 5/8 plug 1.5x Flow Seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 2279 Anhydrite 1918.50 Arbuckle 3815

Dakota. 1400 Plugging Proposal Received by Dale F. Balthezor
879 = 1180 (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None (circled)

Operations Completed: Hour: 8 AM Day: 1 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3815 for 30 mi.

25 SX @ 3815

25 SX @ 1930

100 SX @ 1180 mixed with 1.5x Flow Seal.

40 SX @ 400 dumped 1.5x hulls, pushed plug to 40'

10 SX @ 40

Remarks: 105x in Rat Hole - cementing co. Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-18-84

INV. NO. 2563

7-1

RECEIVED
STATE CORPORATION COMMISSION
Signed Dale F. Balthezor
(TECHNICIAN)
7-9-84

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84

July 6th
20