

6040146

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,000 - 00-00

NE SE NE, SEC. 16, T 6 S, R 21 W/E

1650 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Operator: P.M.I.

Name & Address 400 N. Woodlawn Suite 201

Wichita, Ks. 67208

Lease Name Voss Well # A-1

County Graham

Well Total Depth 3770 122.53 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 363 w/155 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 75

Address _____

Company to plug at: Hour: Noon Day: 26 Month: June Year: 19 84

Plugging proposal received from Don Ryder

(company name) Red Tiger Drilling Company (phone) _____

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk hulls and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part XX None _____

Operations Completed: Hour: 3:15pm Day: 26 Month: June Year: 1984

ACTUAL PLUGGING REPORT Cemented by:

1st plug @ 1950 w/40 sks

2nd plug @ 1050 w/100 sks

3rd plug @ 360 w/40 sks

4th plug @ 40 w/10 sks

10 sks in Rat Hole

RECEIVED STATE CORPORATION COMMISSION

JUL 09 1984

CONSERVATION DIVISION Wichita, Kansas

7-9-84

Remarks: Carl Goodrow witnessed part of this plugging. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-16-84 INV. NO. 2509

Signed Dennis L. Hamel (TECHNICIAN)

7-26 JUL 1 7 10AM