

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-069-02691-00-00

WELL PLUGGING APPLICATION FORM

Well Location NE NE NW Sec. 34 Twp. 6S Rge. _____ (E) _____ (W) 21

Field Name (if any) None County Graham

Lease (Farm Name) Pennington Well No. 1

Was well log filed with application? Yes If not, explain circumstances and give available data (Use an additional sheet if necessary) _____

Plugged on verbal authority of C. T. Alexander.

Date and hour plugging is desired to begin 8:00 A. M. 5-12-43

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired (Use an additional sheet if necessary) No exception

Name of the person on the lease in charge of well for owner _____

C. R. Smith Address Great Bend, Kansas


Name of well owner or Acting Agent Nadel & Gussman

Address Mutual Building, Tulsa, Oklahoma

Invoice covering assessment for plugging this well should be sent to:

Address _____

and payment will be guaranteed by applicant.



PLUGGING
FILE SEC. 34 6S 21W
BOOK PAGE 74 LINE 21

[Signature]
Operator or Acting Agent

Date May 19, 1943

Fennington #1
NE/4 NE/4 NW/4 of Section 34-65-21N
Graham County, Kansas
Hadel & Gussman

15-065-02691-00-00

Commenced: April 23rd, 1943.
 Completed: May 12th, 1943.

Surface clay	0	35
Sand	35	70
Sand and streaks of shale	70	160
Sand, gravel and shale	160	230
Shale, shells & streaks of sand	230	370
Sand and shale	370	440
Shale and shells	440	590
Sand	590	605
Shale and shells	605	900
Shale and streaks of sand	900	995
Sand	995	1030
Shale, red bed and streaks of sand	1030	1095
Sand and shab	1095	1395
red sand	1395	1395
and shale	1395	1375
Sand and streaks of shale	1375	1885
Shale	1885	1905
Line and anhydrite	1905	1934
Shale	1934	1935
Shale and shells	1935	2060
Shale	2060	2250
Line and shale	2250	2350
Shale	2350	2395
Line and shale	2395	2430
Shale	2430	2565
Shale and line	2565	2650
Line	2650	2650
Line and shale	2650	2845
Broken line and shale	2845	2905
Shale and line	2905	3155
White line	3155	3255
Line and shab	3255	3395
Line	3395	3465
Line and shale	3465	3521
F. C. Line	3521	3545
Line	3545	3705
Hard line	3705	3757
Red and green shale-Line streaks	3757	3740
Line and red and green shale	3740	3770
Red shale - line streaks	3770	3784
Sandy line	3784	3788
Cherty line	3788	3795
Red shale - streaks of line	3795	3801
Cherty conglomerate	3801	3805
Conglomerate	3805	3814
Arkuckle dolomite	3814	3824
Arkuckle	3824	3825
TOTAL DEPTH	3825	

STATE OF OKLAHOMA)
)
 COUNTY OF TULSA)

CASING LOG

10-3/4" casing set at 325' and cemented
 with 500 sacks of cement.

PLUGGING
 FILE NO. 34 6 21W
 BOOK PAGE 74 21

I hereby affirm that the above and foregoing is a true and correct copy of the log of
 your Fennington Well #1, located in the Northeast Quarter of the Northeast Quarter of the
 Northwest Quarter of Section 34, Township 6 South, Range 21 West, Graham County, Kansas.

HELMERICH & BAYNE, INC.

By William B. Bayne
 Treasurer

Subscribed and sworn to before me, a Notary Public, this 17th day of May, 1943.

Leo Huffer
 Notary Public

My commission expires
 July 22nd, 1943



15-069-02691-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

800 BITTING BUILDING
WICHITA, KANSAS

May 13, 1945

IN REPLY PLEASE
REFER TO THIS
SUBJECT

Well No. 1
Farm Pennington
Description NRC NW 34-8-21
County Graham
File 74-21

Nadel & Gussman
402 Union National Bank Bldg.
Wichita, Kansas

Dear Sirs:

This letter is your permit to plug
the above subject well, in accordance
with the Rules and Regulations of the
STATE CORPORATION COMMISSION.

Yours very truly,

STATE CORPORATION COMMISSION

T. A. MORGAN, DIRECTOR
CONSERVATION DIVISION

HA

By: J. P. Roberts
J. P. ROBERTS

NOTICE:

C. T. Alexander
Box 445
Great Bend, Kansas