

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER ¹⁵⁻ 065-22,233 -00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Foxfire Exploration, Inc. OPERATORS LICENSE NO. 6177

ADDRESS 1022 Union Center, Wichita, Kansas 67202 PHONE # (316) 265-6296

LEASE (FARM) Gudgell WELL NO. 1 WELL LOCATION SE SW SE COUNTY Graham

SEC. 4 TWP. 6S RGE. 22W (E) or (W) (W) TOTAL DEPTH 3860 PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 210' CEMENTED WITH 150 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug @ 3810' w/25 sx; 2nd plug @ 1950'
w/25 sx; 3rd plug @ 1160' w/100 sx & 1 sx celloflake; 4th plug @ 240' w/40 sx; 5th plug @ 40'
w/10 sx; 10 sx in rathole. Total 210 sx 60/40 poz, 6% gel, 3% cc.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN October 7, 1985, 4:00 AM

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Foxfire Drilling Co., Inc. PHONE # (316) 265-6296

ADDRESS 1022 Union Center, Wichita, Kansas

PLUGGING CONTRACTOR Foxfire Drilling Co., Inc. LICENSE NO. 8430

ADDRESS Same PHONE # () Same

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Dorine J. Staw
STATE CORPORATION COMMISSION (Operator or Agent)

DATE: November 4, 1985

OCT 21 1985
10-25-85
CONSERVATION DIVISION