

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

FORM CP-1  
Rev. 03/92

130 S. Market, Room 2078  
Wichita, Kansas 67202

RECEIVED  
APR 05 2005  
KCC WICHITA

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-185-233704-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: Mull Drilling KCC LICENSE # 5144  
(owner/company name) (operator's)

ADDRESS: P.O. Box 2758 CITY: Wichita  
STATE: Kansas ZIP CODE: 67201-2758 CONTACT PHONE: 316-264-6366  
LEASE: Hall "G" WELL#: 1-11 Section 11 Township 21s Range 13w  
SE NW SE SE SPOT LOCATION/QQQQ COUNTY: Stafford

800 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)  
800 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ D&A XX SWD/ENHR WELL \_\_\_\_\_ Docket # \_\_\_\_\_  
CONDUCTOR CASING SIZE None SET AT NA CEMENTED WITH NA SACKS  
SURFACE CASING SIZE 8-5/8" SET AT 295' KB CEMENTED WITH 275 SACKS  
PRODUCTION CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:  
ELEVATION 1863.1 G.L. 1872.1 K.B. T.D. 3678 PBDT \_\_\_\_\_ Anhydrite Depth 693  
(Stone Corral Formation)  
CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING:  
Plugged well on 04/01/05 in this manner: Heavy mud in hole and between all plugs. Used 175 sx of 60/40 Poz,  
6% Gel. Bottom plug at 3540' - 50 sx, 2nd plug at 720' - 50 sx, 3rd plug at 330' - 50 sx, top plug at 40' - 10 sx  
Rathole - 15 sx, no mousehole. Job completed at 4:30 pm on 04/01/05. Allied Cementing ticket #20060.  
Sterling reported plugging to KCC 04/04/05 (Mike Maier).  
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)  
If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Lonnie Saloga Phone#: (620) 672-9508  
Address: P.O. Box 1006 City: Pratt State: Kansas  
PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142  
(company name) (contractor's)  
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 4:30 am on April 1, 2005.  
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Plugged Operator X Agent \_\_\_\_\_

DATE: 04/01/05 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott  
(signature) Gary M. Talbott, Agent for Operator

# Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

## Hall "G" 1-11

**LOCATION:** SE NW SE SE  
**API:** 15-185-233304-0000

Section 11 T 21s R 13w  
Stafford County, Kansas

**OWNER:** Mull Drilling  
**CONTRACTOR:** Sterling Drilling Company, Rig #1

**COMMENCED:** 21-Mar-05  
**COMPLETED:** 01-Apr-05

**TOTAL DEPTH:** **DRILLER** 3678 FEET  
**LOGGER** 3677 FEET

**Ground Elevation:** 1863  
**KB Elevation:** 1872

### LOG

0 -	3 FEET	Top Soil	From Water Well Driller
3 -	28 FEET	Clay	
28 -	50 FEET	Fine Sand	
50 -	86 FEET	Sand and Gravel	
86 -	240 FEET	Sand, Gravel and Clay	
240 -	693 FEET	Redbeds	
693 -	722 FEET	Anhydrite (Driller's)	
722 -	1670 FEET	Shales and Salt	
1670 -	3540 FEET	Limestone, Shale and Dolomite	
3540 -	3678 FEET	Arbuckle	

### CASING RECORDS

#### Surface Casing-8-5/8"

Spud at 7:15 pm on 03/21/05. Drilled 12-1/4" hole to 295'. Ran 7 joints of 8-5/8" surface casing, tallied 280', set 6' below ground level at 295' KB. Cemented with 275 sx 70/30 Poz, 3% CC, & 2% Gel. Cement did circulate. Plug down at 5:30 am on 03/22/05. Allied Cementing ticket # 20053. Welder strapped bottom 3 joints together and welded collars on remaining joints.

#### Production Casing

Plugged well on 04/01/05 in this manner: Heavy mud in hole and between all plugs. Used 175 sx of 60/40 Poz, 6% Gel. Bottom plug at 3540' - 50 sx, 2nd plug at 720' - 50 sx, 3rd plug at 330' - 50 sx, top plug at 40' - 10 sx Rathole - 15 sx, no mousehole. Job completed at 4:30 pm on 04/01/05. Allied Cementing ticket #20060. Sterling reported plugging to KCC 04/04/05 (Mike Maier).

### DEVIATION SURVEYS

3/4	degree(s) at	295	feet
3/4	degree(s) at	2218	feet
1	degree(s) at	3337	feet
1	degree(s) at	3520	feet
1	degree(s) at	3551	feet
3/4	degree(s) at	3678	feet

RECEIVED  
APR 05 2005  
KCC WICHITA