

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2070
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-065-23037-00-00

LEASE NAME Quint C

TYPE OR PRINT
NOTICE: Fill out completely
and return to Comm. Div.
office within 30 days.

WELL NUMBER 2

2,310 Ft. from S Section Line

750 Ft. from ^W Section Line

SEC. 20 TWP. 8S ROR. 22 XXXor(W)

COUNTY Graham

Date Well Completed 3-22-05

Plugging Commenced 3-22-05

Plugging Completed 3-23-05

LEASE OPERATOR Russell Oil Inc.

ADDRESS PO Box 1469, Plainfield, IL 60544

PHONE#(815) 609-7000 OPERATORS LICENSE NO. 3293

Character of Well D & A

(Oil, Gas, DAA, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-22-05 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D. 3,650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	217'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each so. Push plug to 1,785', pump 25 sax cement on plug thru drill pipe; push plug to 925', pump 100 sax cement on plug thru drill pipe; push plug to 275', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address PO Box 709, Russell, KS 67665

RECEIVED

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Russell Oil, Inc.

MAR 30 2005

STATE OF KANSAS COUNTY OF RUSSELL, ss.

KCC WICHITA


Jack P. Beeman, Sec.-Treas. Contractor
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God. SHIELDS DRILLING CO.

(Signature) Jack P. Beeman

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 28th day of March, 2005

My Commission Expires:



Notary Public