

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Merkel, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15051-19095-0000

LEASE NAME Wiles

WELL NUMBER 4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 16 TWP. 11S RGE. 19 (E) or (41)

LEASE OPERATOR Berexco, Inc.

ADDRESS P.O. Box 723 Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well oil

(Oil, Gas, O&A, SMD, Input, Water Supply Well)

COUNTY Ellis 113

Date Well Completed 10-8-64

Plugging Commenced 3-1-05

Plugging Completed 3-4-05

KCC
BEM
4-5-05
RBDMS
CP243

The plugging proposal was approved on _____ (date)
by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Arb. Depth to Top _____ Bottom _____ T.D. 3506

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:
Tie onto 5 1/2 csg - pump 35 bbl - circ to surf. in 8 5/8 csg. Run 113 Jts 2 3/8 tbg. to 3430
Mix 50 sx cement 2% calcium w/ 200# hulls. Pull tbg. shoot csg collar @ 1979. work csg. to
6500 - NOT FREE. Shoot 5 1/2 collar @ 1946. worked free. 18' pulled out leading it 4 bl its 5 1/2 14# csg.
Run 2 3/8 tbg. to 1885. Mix 120 SX 60/40 Poz 10% gel w/ 500# hulls. Pull tbg to 1250' Mix 100 SXS. 60/40 Poz 10% gel
Pull tbg to 750' Circ to surf w/ 115 sx Pull tbg. 8 5/8 stayed full of cement from cellar Jay Pfeifer rec Hays 11:30 AM

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address P.O. Box 723 Hays, KS 67601

RECEIVED

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

MAR 30 2005

STATE OF Kansas COUNTY OF Ellis, ss.

KCC WICHITA

Curt Gabel (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Curt Gabel

(Address) P.O. Box 723 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 25th day of March, 2005

Marion Sue Vance
Notary Public

My Commission Expires: 4-30-06



Form CP-4
Revised 05-88

Ber