

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form**  
Form must be Signed  
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION  
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226  
Phone: (316) 682-1537 Operator License #: 5030

Type of Well: ENHR Docket #: #12,545  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

<u>Toronto</u>	Depth to Top: <u>3098</u>	Bottom: <u>3103</u>	T.D. _____
<u>LKC</u>	Depth to Top: <u>3120</u>	Bottom: <u>3299</u>	T.D. <u>3361</u>
<u>Arbuckle</u>	Depth to Top: <u>3381</u>	Bottom: <u>3446</u>	T.D. <u>3446</u>

API Number: 15-NA/63-03953-00-01

Lease Name: Reeder

Well Number: #1

Spot Location (QQQQ): \_\_\_\_\_ - NW - NW - SE

2310' Feet from  North /  South Section Line

2310' Feet from  East /  West Section Line

Sec. 19 Twp. 8S S. R. 17W  East  West

County: Rooks

Date Well Completed: 18

Plugging Commenced: 3/10/05

Plugging Completed: 3/10/05

*KCC  
BEM  
4-5-05  
RBDms  
CP 2/3*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	234'	
				5-1/2	3780'	
				DV	1753'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged and abandoned as follows: MIRU. TIH w/tubing to 3000'. Spotted 50 sx 60/40 poz w/10% gel w/300# hulls and 24 sx gel on top. Pull tbg to 1350'. Circulated 90 sx same cement w/300# hulls to surface. TOH w/tbg. Tied onto 5 1/2" and pumped 35 sx cement. MP - 300#. Pressured up on 8 5/8" to 600#.

Approved by Dennis Hamel w/KCC.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: 99996

Address: P.O. Box 31, Russell, KS 67665-0031

**RECEIVED  
APR 01 2005**

Name of Party Responsible for Plugging Fees: Vess Oil Corporation **KCC WICHITA**

State of Kansas County, Sedgwick, ss.


Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Pat Canaday*

(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 31st day of March  
*Michelle D. Tierning* My Commission Expires \_\_\_\_\_  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*B*

# WELL RECORD

Company..... Cities Service Oil Company..... Well No. .... 1..... Farm ..... Reeder  
 Location..... 330' South and 350' East of Center..... Sec. .... 19..... T. .... 8..... R. .... 17W  
 Elevation..... 1958 (1955 Gr.)..... County..... Rooks..... State..... Kansas  
 Drlg. Comm. .... December 12, 1951..... Contractor..... Holm Drilling Company  
 Drlg. Comp. .... January 8, 1952..... Acid..... 5000 gals. (see below)  
 T. D. .... 3394'..... Initial Prod. .... Physical Potential: 40 oil, 1 water, 24 hrs. (2-20-52)

CASING RECORD:

8-5/8" @ 258' cem. 175 sx cement  
 5-1/2" @ 3381' cem. 150 sx cement

D-V tool at 1309' with 300 sx cement  
 and 38 sacks stratacrete.

FORMATION RECORD:

surface clay & lime	0-40
clay	80
shale & shells	255
shale	258
shale & shells	765
sand	1035
shale & shells	1280
lime	1325
shale	1500
shale & shells	1630
salt, shale & shells	1770
shale & shells	1950
lime & shale	2085
lime	2180
lime & shale	2600
shale & lime	2765
lime & shale	2932
lime	3358
conglomerate	3376
lime	3384
lime	3384 RTD = 3383 SIM
lime	3394 T. D.

Corr. Heebner	3076'
Corr. Dodge	3097'
Corr. Lansing	3118'
Corr. Arbuckle	3379'
Penetration	15'
Total Depth	3394'

312' oil in 11 hrs. at T. D. 3388.  
 1-1-52 Acidized 1000 gals. at T. D. 3388.  
 1-4-52 Pumped 33 oil, 1% acid wtr. 24 hrs.  
 1-4-52 Acidized 2000 gals.  
 1-7-52 Pumped 40 oil, 2 acid wtr., 24 hrs.  
 1-8-52 Deepened 3388-3394.  
 1-9-52 Acidized 2000 gals.

SIFO:	1000'	1°	<b>RECEIVED</b> <b>APR 01 2005</b> <b>KCC WICHITA</b>
	1500'	1°	
	2000'	1°	
	2500'	0°	

7-7/8" rotary hole.

H-1-60 Deepened 3394-3446'  
 & acidized / 1500 gal  
 from 3392 to 3403'

# ALLIED CEMENTING CO., INC. 18687

Federal Tax I.D. ~~19-0000000~~

SHIP TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Russell

DATE <u>3-10-05</u>	SEC. <u>19</u>	TWP. <u>8</u>	RANGE <u>17</u>	CALLED OUT <u>9:00AM</u>	ON LOCATION <u>9:30AM</u>	JOB START <u>9:45AM</u>	JOB FINISH <u>12:01PM</u>
LEASE <u>Reeder</u>	WELL # <u>1W</u>	LOCATION <u>PLAINVILLE N TO RD 9.</u>			COUNTY <u>ROOKS</u>	STATE <u>KANSAS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>2 1/2 E 1/2 N 1/2 W</u>			

CONTRACTOR Co. Tools

TYPE OF JOB Plug ABANDONED well

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2 DEPTH \_\_\_\_\_

TUBING SIZE 2" DEPTH 3000'

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL DV TOOL DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE 500# SHOE JOINT 300#

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_

CEMENT (USED 175 SK)

AMOUNT ORDERED 225 SK 60/40 10%g

600# Hull's

COMMON	<u>105 SK</u>	@	<u>8.30</u>	<u>871.5</u>
POZMIX	<u>70 SK</u>	@	<u>4.50</u>	<u>315.</u>
GEL	<u>39 SK</u>	@	<u>13.00</u>	<u>507.</u>
CHLORIDE	_____	@	_____	_____
ASC	_____	@	_____	_____
<u>Hull's</u>	<u>6 SK</u>	@	<u>20.00</u>	<u>120.</u>

EQUIPMENT

PUMP TRUCK CEMENTER Gleam

# 366 HELPER Shane

BULK TRUCK

# 213 DRIVER Keith

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

RECEIVED

APR 01 2005

KCC WICHITA

HANDLING	<u>269 SK</u>	@	<u>6.50</u>	<u>403.</u>
MILEAGE	<u>55 ton mile</u>	@	<u>.055</u>	<u>817.5</u>
TOTAL				<u>3031.0</u>

REMARKS:

2" Tubing @ 3000' Spot 24 SK GEL + 50 SK Cement w/ 300# Hull's. Pulled up to 1350 & Circ. Cement to SURFACE w/ 90 SK Cement & 200# Hull's. Pull Tubing 5 1/2 SWAGE Squeezed in ANOTHER 35' SK w/ 100# Hull's @ 500# MAX PSI Shot in @ 300#. 8 1/2" COULD NOT Pump INTO @ 600#.

THANK'S

CHARGE TO: Vess Oil Co.

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

SERVICE

DEPTH OF JOB	_____			
PUMP TRUCK CHARGE	_____			<u>570.</u>
EXTRA FOOTAGE	_____	@		
MILEAGE	<u>55</u>	@	<u>4.50</u>	<u>247.</u>
MANIFOLD	_____	@		
TOTAL				<u>817.5</u>

~~\_\_\_\_\_~~

~~\_\_\_\_\_~~

~~\_\_\_\_\_~~

~~\_\_\_\_\_~~

~~\_\_\_\_\_~~

PLUG & FLOAT EQUIPMENT

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX	_____			
TOTAL CHARGE	_____			
DISCOUNT	_____			IF PAID IN 30 D
TOTAL				_____

PRINTED NAME \_\_\_\_\_