

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8/10/04 (Date)
by: David Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3780 Bottom: 3781 T.D. 3781
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-NA-01471-00-00
Lease Name: Morel B
Well Number: #8
Spot Location (QQQQ): _____ - SE - SW - NE
2310' Feet from North / South Section Line
1650' Feet from East / West Section Line
Sec. 22 Twp. 9S S. R. 21 East West
County: Graham
Date Well Completed: 1/52
Plugging Commenced: 3/8/05
Plugging Completed: 3/8/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	234'	
				5-1/2"	3780'	
					ENHR	
				DV - 1753	w/394 sx	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plug and abandoned as follows: MIRU. TIH w/tbg to 3600' FS. Spotted 50 sx 60/40 poz w/10% gel and 300# hulls and 24 sx gel on top. Pulled tbg to 1750' FS. Spotted another 50 sx same cement w/100# hulls. Pulled tbg to 950' FS. Spotted another 70 sx same cement w/200# hulls, cement circulated to surface. TOH w/tbg. Tied onto 5 1/2" csg and pumped 10 sx cement. MP - 500#, SIP - 500#. Tied onto 8 5/8" and pumped 10 sx cement. MP - 500#, SIP - 500#. Plugging approved by Dennis Hamel w/KCC.


Name of Plugging Contractor: Allied Cementing Co., Inc. License #: _____
Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.

Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 30th day of March
Michelle D. Henning My Commission Expires _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 31 2005
KCC WICHITA

[Signature]

WELL RECORD

Company Cities Service Oil Company Well No. 3 Farm Morel #1
 Location 330' North and 990' E. of Center Sec. 22 T. 9 R. 21W
 Elevation 2286 (2284 Cr.) County Graham State Kansas
 Drlg. Comm. December 28, 1951 Contractor R. W. Rine Drilling Company
 Drlg. Comp. January 5, 1952 Acid None
 T. D. 3781' Initial Prod. Physical Potential: 156 oil, 40% water, 2 1/2 hrs. (3-10-52)

CASING RECORD:

8-5/8" @ 234' con. 175 sz cement
 5-1/2" @ 3780' con. 175 sz cement and
 D-7 tool at 1753' with
 350 sz cement and 44 sz
 Stratacrete.

FORMATION RECORD:

surface clay & sand	0-40
sand, clay & shale	234
shale	600
shale & shells	1425
shale	1730
anhydrite	1785
shale & shells	2150
shale, shells & lime	2385
shale & lime	2525
shale & broken lime	2730
shale & lime	2850
lime & shale	3375
lime	3654
lime & shale	3762
lime	3783

3783 RTD = 3781 SDH

Corr. Hooker	3443'
Corr. Dodge	3489'
Corr. Lansing	3482'
Corr. Simpson	3766'
Corr. Arbuckle	3779'
Penetration	2'
Total Depth	3781'

Fillup: 60' oil in 20 mins.
 95' oil in 30 mins.
 1066' oil in 1 hr. 30 mins.
 1342' oil in 2 hrs.

1-17-52 Pumped 118 oil, 19 water,
 24 hrs.

SIFO: 500' 2°
 1000' 1°
 1500' 2°
 2000' 1°
 2500' 1°
 3000' 1°
 3500' 0°

RECEIVED
MAR 31 2005
KCC WICHITA

7-7/8" rotary hole.

3-11-52 E.D. To bottom

ALLIED CEMENTING CO., INC. 18622

Federal Tax I.D.# ~~00-0000000~~

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

DATE <u>3-8-05</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>10:00am</u>	JOB START <u>10:30am</u>	JOB FINISH <u>12:30pm</u>
LEASE <u>NO PELL</u>	WELL # <u>B-8</u>	LOCATION <u>CHURCH OF GOD 134N</u>			COUNTY <u>OSAWATOMIE</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>RUSSEL</u>			

CONTRACTOR SMOKEY HILL
 TYPE OF JOB PTA
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2 DEPTH _____
 TUBING SIZE 2" DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER _____
 CEMENT
 AMOUNT ORDERED 300 4 1/2 10% CEL
24 CEL 6 HULLS
USED 200 SK

EQUIPMENT
 PUMP TRUCK CEMENTER MARK
 # 177 HELPER PAUL
 BULK TRUCK
 # 378 DRIVER CARV
 BULK TRUCK
 # _____ DRIVER _____

COMMON	<u>120</u>	@	<u>830</u>	<u>996.00</u>
POZMIX	<u>80</u>	@	<u>450</u>	<u>360.00</u>
GEL	<u>40</u>	@	<u>130</u>	<u>520.00</u>
CHLORIDE		@		
ASC		@		
		@		
<u>HULLS</u>	<u>6</u>	@	<u>20.00</u>	<u>120.00</u>
RECEIVED				
MAR 31 2005				
KCC WICHITA				
HANDLING	<u>351</u>	@	<u>1.00</u>	<u>526.00</u>
MILEAGE	<u>5 1/2 * SK/MILE</u>			<u>125.13</u>
				TOTAL <u>3777.65</u>

REMARKS:

24 CEL 50 cem w/3 HULLS @ 3500'
50 SK w/1 HULL @ 1750
70 SK @ 950 CIRC CEMENT
PULLED TUBING TIED ONTO
5 1/2 WITH 10 SK - PRES TO 500'
MIX 10 SK DOWN 8 1/2 - PRES TO 500'

CHARGE TO: VESS
 STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE 

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>570.00</u>
EXTRA FOOTAGE	@		
MILEAGE	<u>65</u>	@	<u>450</u>
MANIFOLD	@		
	@		
	@		
TOTAL <u>862.00</u>			

PLUG & FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		
TOTAL _____			

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____