

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: American Warrior Inc.

Address: P.O. Box 399 Garden City Ks. 67846

Phone: (620) 275-2963 Operator License #: 4058

Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3/10/05 (Date)

by: Pat Staab (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Lansing Depth to Top: 3126' Bottom: 3140' T.D. 3348'

Cong Depth to Top: 3301' Bottom: 3307' T.D. 3348'

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 051-22914 - 00 - 00

Lease Name: Glick

Well Number: #1

Spot Location (QQQQ): C - NW - NW - SE

2310' Feet from  North /  South Section Line

2310' Feet from  East /  West Section Line

Sec. 22 Twp. 11 S. R. 16  East  West

County: Ellis

Date Well Completed: 6/1/82

Plugging Commenced: 3/10/05

Plugging Completed: 3/10/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				85/8	217'	0
				41/2	3378'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 1347', 975' and 525'. Swift hooked up and pumped 135sx SMD cement with 500# of hulls. Shut in pressure 400#.

Hooked up to surface and pressured to 1000# held. Cut casing off 6' below surface, Capped and back filled.

Name of Plugging Contractor: Swift Services Inc. License #: 32382

Address: P.O. Box 466 Ness City Ks. 67560

Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss.

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 399 Garden City Ks. 67846

**DEBRA J. PURCELL**  
Notary Public - State of Kansas  
My Appt. Expires 11/1/07

DESCRIBED and SWORN TO before me this 1 day of April, 20 05

[Signature] My Commission Expires: 11/1/07  
Notary Public

RECEIVED  
APR 04 2005  
KCC WICHITA

[Handwritten mark]