

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Anadarko E&P Company LP

Address: 1201 Lake Robbins Dr, The Woodlands, TX 77380

Phone: (832) 636-3128 Operator License # 6417 33136

Type of Well: Oil Docket # (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: Jim Holland (Date)

by: 10/29/04 (KCC District Agent's)

Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [ ] No

Producing Formation(s): List All (If needed attach another sheet)

Morrow Depth to Top: 4726 Bottom: 4775 T.D. 4950

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number 15- 055-20600-00-00

Lease Name Piney

Well Number 4

Spot Location (QQQQ) S/2 NE NW

4250 Feet from [ ] North [X] South Line of Section

3300 Feet from [ ] East [X] West Line of Section

Sec. 20 Twp. 23 S. R. 34 [ ] East [X] West

County: Finney

Date Well Completed: 7/15/85

Plugging Commenced: 10/29/04

Plugging Completed: 10/30/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out). Row 1: Morrow, Oil, 0, 4949', 5-1/2", 4949', 0-4'.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 4100' and spot 5 sxs cement on top of CIBP. Spot plug with 25 sxs of cement at 1950'. Cement production with cement plug of 145 sxs from 1150' to surface. Spot heavy mud between cement plugs.

Set 15 sxs of cement into surface casing and tested at 300 psi. Cut surface casing and production casing 4' below G1.

Name of Plugging Contractor: Eagle Well Services License # 7407


Address P. O. Box 1597, Liberal, KS 67901

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Jerry N. Blossom (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) 1201 Lake Robbins Dr., The Woodlands, TX 77380

MY COMM. EXP. DECEMBER 3, 2005 and SWORN TO before me this 1 day of April, 2005

[Handwritten Signature] My Commission Expires: 12-3-05