

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

**Well Plugging Record**  
**K.A.R. -82-3-117**

API NUMBER 15-185-233304-0000  
LEASE NAME Hall "G"  
WELL NUMBER 1-11

23304-00-00

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

800 Ft. from South Line of Section  
800 Ft. from East Line of Section

LEASE OPERATOR Mull Drilling SPOT LOCATION SE NW SE SE  
ADDRESS P.O. Box 2758 Section 11 Township 21s Range 13w  
CITY, STATE, ZIP Wichita, Kansas 67201-2758 County Stafford  
PHONE # 316-264-6366 Date Well Completed 04/01/05  
Character of Well Dry and Abandoned Date Plugging Commenced 04/01/05  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 04/01/05

The plugging proposal was approved on April 1, 2005 (date)  
by Richard Lacey (KCC District Agent's Name)

Is ACO-1 Filed? \_\_\_\_\_ If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 3678

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	240			
Redbeds	Shale	240	693	8-5/8"	280'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged well on 04/01/05 in this manner: Heavy mud in hole and between all plugs. Used 175 sx of 60/40 Poz, 6% Gel. Bottom plug at 3540' - 50 sx, 2nd plug at 720' - 50 sx, 3rd plug at 330' - 50 sx, top plug at 40' - 10 sx Rathole - 15 sx, no mousehole. Job completed at 4:30 pm on 04/01/05. Allied Cementing ticket #20060. Sterling reported plugging to KCC 04/04/05 (Mike Maier).

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mull Drilling (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.


Gary Talbott (Employee of Operator or (Operator) of above described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of  
the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary Talbott*

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 4th day of April 2005

*Pamela S. Fields*  
(Notary Public)



My Commission Expires \_\_\_\_\_

Form CP-4  
Revised 12-92

**RECEIVED**  
**APR 05 2005**  
**KCC WICHITA**

*B...*

# Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

Hall "G" 1-11

**LOCATION:** SE NW SE SE Section 11 T 21s R 13w  
**API:** 15-185-233304-0000 Stafford County, Kansas

**OWNER:** Mull Drilling  
**CONTRACTOR:** Sterling Drilling Company, Rig #1

**COMMENCED:** 21-Mar-05

**COMPLETED:** 01-Apr-05

**TOTAL DEPTH:** **DRILLER** 3678 FEET  
**LOGGER** 3677 FEET

**Ground Elevation:** 1863

**KB Elevation:** 1872

## LOG

0 -	3 FEET	Top Soil	From Water Well Driller
3 -	28 FEET	Clay	
28 -	50 FEET	Fine Sand	
50 -	86 FEET	Sand and Gravel	
86 -	240 FEET	Sand, Gravel and Clay	
240 -	693 FEET	Redbeds	
693 -	722 FEET	Anhydrite (Driller's)	
722 -	1670 FEET	Shales and Salt	
1670 -	3540 FEET	Limestone, Shale and Dolomite	
3540 -	3678 FEET	Arbuckle	

## CASING RECORDS

### Surface Casing-8-5/8"

Spud at 7:15 pm on 03/21/05. Drilled 12-1/4" hole to 295'. Ran 7 joints of 8-5/8" surface casing, tallied 280', set 6' below ground level at 295' KB. Cemented with 275 sx 70/30 Poz, 3% CC, & 2% Gel. Cement did circulate. Plug down at 5:30 am on 03/22/05. Allied Cementing ticket # 20053. Welder strapped bottom 3 joints together and welded collars on remaining joints.

### Production Casing

Plugged well on 04/01/05 in this manner: Heavy mud in hole and between all plugs. Used 175 sx of 60/40 Poz, 6% Gel. Bottom plug at 3540' - 50 sx, 2nd plug at 720' - 50 sx, 3rd plug at 330' - 50 sx, top plug at 40' - 10 sx Rathole - 15 sx, no mousehole. Job completed at 4:30 pm on 04/01/05. Allied Cementing ticket #20060. Sterling reported plugging to KCC 04/04/05 (Mike Maier).

## DEVIATION SURVEYS

3/4	degree(s) at	295	feet
3/4	degree(s) at	2218	feet
1	degree(s) at	3337	feet
1	degree(s) at	3520	feet
1	degree(s) at	3551	feet
3/4	degree(s) at	3678	feet

RECEIVED  
APR 05 2005  
KCC WICHITA