

11-4-87

6 030996

API NUMBER 15- 065-22,420 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW SE, SEC. 36, T 6 S, R 21 W/E

990 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8000

Lease Name LeSage Well # 1 34-36

Operator: Pan Canadian Petroleum Co.
Name & Address: 600 17th Street Suite 1800
Denver, Colorado 80202

County Graham 121.23

Well Total Depth 3730 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 313

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Wichita, Kansas

Company to plug at: Hour: AM Day: 4 Month: Nov Year: 19 87

Plugging proposal received from Lloyd Dellett

(company name) Murfin Drilling Co., (phone)

were: 8 5/8" set at 313' w/200 sks cwc. Circulate hole with no less than 36 vis mud with no loss or gain of fluid. Spot cement plugs with drill pipe and balance all plugs with mud. Order 190 sks 60/40 Poz 6% Gel 3% C C, 8 5/8 wiper plug. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00AM Day: 4 Month: Nov Year: 19 87

ACTUAL PLUGGING REPORT Spot cement plugs at 1800' w/25 sks

1050' w/100 sks 1 sk Hulls

360' w/40 sks

Push wiper plug to Kelly depth fill w/10 sks

Circ 15 sks in rat hole w/joint of pipe

Anhy 1790' - 1823' Elev 2173'

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (copy) to observe this plugging.

DATE 1-7-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 19395

Carl Goodrow

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
DEC 16 1987

JAN 14 1988

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 10 28 87 month day year

API Number 15- 065-22,420 ~00-0 C

OPERATOR: License # 8000
Name: PanCanadian Petroleum Company
Address: 600 17th Street, Suite 1800
City/State/Zip: Denver, CO 80202
Contact Person: Tom Rubis
Phone: 303-825-8371

NE SW SE Sec. 36 Twp. 6 S, Rg. 21 X West
990 Ft. from South Line of Section
1650 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6033
Name: Murfin Drilling Company
City/State: Wichita, KS

Nearest lease or unit boundary line 990 feet
County: Graham
Lease Name: LeSage Well # 1 34-36
Ground surface elevation 2173 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj X Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 200
Depth to bottom of usable water 1200
Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 250
Conductor pipe required N/A
Projected Total Depth 3900 feet
Formation BKC

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications
Date 10-27-87 Signature of Operator or Agent Rob Ramsey Agent for Operator Title Ass't. Drlg. Mgr.

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2
This Authorization Expires 4-27-88 Approved By RCH 10-27-87

EFFECTIVE DATE: 11-1-87 Comp 6 AM 11-4-87

Lloyd Deleate

SP 313/20041

NE SW SE Sec. 36 Twp. 6 S, Rg. 21 X West

TD 3730 plus 11-2-87
only 1790 1823 PLUGGING PROPOSAL IF ABOVE IS D & A ELEV 2173 1050
1400

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 3900 1800 feet depth with 25 sxs of .60-40. Poz. 6% gel. 3 Acc
2nd plug @ 1650 feet depth with 20 sxs of "
3rd plug @ 250 1050 feet depth with 100 sxs of "
4th plug @ 300 360 feet depth with 40 sxs of "
5th plug @ 40 w.p. feet depth with 10 sxs of "
(2) Rathole with 15 sxs (b) Mousehole with sxs

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging. In Addition: Call district office after well is either plugged or production casing is cemented in. (Call 7 a.m. to 5 p.m. workdays)

District office use only:
API #15- 065-22,420
Surface casing of feet set with sxs at hours, 19
Alternate 1 or 2 surface pipe was used.
Alternate 2 cementing was completed @ ft. depth with sxs on 19
Hole plugged 19, agent

STATE OF KANSAS
12-16-87
DEC 16 1987
CONSERVATION DIVISION
Wichita, Kansas

received KCC District #6 OCT 28 1987 Hays, KS
KCC District #6 OCT 28 1987 Hays, KS
Form C-1 1285