

4-031691

4-28

168  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,675 0000

SW NE SE /4 SEC. 35, 06 S, 21 W  
1650 feet from S section line  
990 feet from E section line

Operator license# 4767

Lease Parker "C" well # 1

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market  
#1000  
Wichita, Kansas 67202

Well total depth 3690 feet <sup>179.92</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 252 feet

Aband. oil well    , Gas well    , Input well    , SWD    , D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 28 Month: April Year: 92

Plugging proposal received from: Lloyd Dellett

Company: Murfin Drilling Company Phone:                     

Were: Order 200 sx. 60/40 pozmix - 6% gel. - 3% c.c.  
Allied Cement Company.  
8 5/8" set @ 252' w/170 sx. cwc.  
Condition hole.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[     ], Part[     ], None[ X ]

Completed: Hour: 11:45P.M., Day: 28, Month: April, Year: 92

Actual plugging report:

Spot plugs with drill pipe w/25 sx. @ 1850'.  
w/100 sx. @ 1100' with hulls.  
w/40 sx. @ 300'.  
w/10 sx. @ 40' W.P.  
Circulate 15 sx. in rathole.  
Circulate 10 sx. in mousehole.

Remarks:

Condition of casing(in hole): GOOD     BAD     Any plug: YES X NO    

Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES    , NO    

Plugged through TUBING    , CASING    . Elevation: 2222 GL    

I did [     ] did not [ X ] observe the plugging.

DATE 6-3-92

INV. NO. 35371

Carl Goodrow

(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 11 1992  
CONSERVATION DIVISION  
Wichita, Kansas