

4-061047 2-10

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-22,782 -0000
125' N. of
SE SE NW /4 SEC. 33, 06 S, 21 W
3095 feet from S section line
2970 feet from E section line

Operator license# 31523

Lease Johnson B Well # 2

Operator: Raney Oil Company

County: Graham 116.35

Address: 3425 Tam O'Shanter
Lawrence, Kansas 66047

Well total depth 3580 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 273 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Duke Drilling Company License# 5929

Address: Wichita, Kansas 67202

Company to plug at: Hour: 9:45 P.M. Day: 10 Month: February Year: 1997

Plugging proposal received from: Mike Godfrey

Company: Duke Drilling Company Phone:

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.
TD in LKC.

RECEIVED
KANSAS CORP COM
1997 FEB 19 P 2:02

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 11:45 P.M. Day: 10 Month: February Year: 1997

Actual plugging report:

- 1st. Plug at 1900' w/25 sxs. Anhydrite 1876' - 1908'.
- 2nd. Plug at 1140' w/100 sxs. Dakota 838' - 1138'.
- 3rd. Plug at 325' w/40 sxs. Surface pipe at 273'.
- 4th. Plug at 40' w/10 sxs.
- 15 sxs in rathole.
- 10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2238 GL

I did / did not X observe the plugging.

[Signature]
(agent)
Form CP-2/3

INVOICED
DATE FEB 20 1997
INV. NO. 47613

2-19-97