

6-25 4-050193

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,737 ~00-00

S2 NW SW /4 SEC. 05, 06 S, 22 W
1650 feet from S section line
4620 feet from E section line

Operator license# 5663

Lease Rouback well # 1

Operator: Hess Oil Company

County Graham

Address: P.O. Box 1009
McPherson, Kansas 67460
316-241-4640

Well total depth 3750 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 inch @ 213 feet

121.87

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Allied Cementing License#

Address:

Company to plug at: Hour: PM Day: 25 Month: June Year: 1994

Plugging proposal received from: Carol Nickel

Company: Mallard Drlg. Co. phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2000 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1190 feet " 100 " Mouse hole: 10 sacks

3rd plug @ 265 feet " 40 "

4th plug @ 40 feet " 10 " with 8 5/8" wiper plug

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 11:15 PM, Day: 25, Month: June, Year: 1994

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sk

Remarks: Elevation: 2287, Anhydrite: 1980-2010 feet, Anhydrite plug: 2000
Bottom plug (in place): Yes X, Calc , No Arbuckle: None

Did NOT penetrate Arbuckle, cemented by Allied Cementing

I did not [X] observe the plugging.

INVOICED

DATE JUL 06 1994

INV. NO. 40754

6-25

Marvin L. Miller P.L.R.T.II
(agent)

Form CP-2/3

6-30-94
RECEIVED
JUN 30 1994
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas