

8-15

4-061098

-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-22,787
NW NW NE /4 SEC. 14, 06 S, 22 W
4950 feet from S section line
2310 feet from E section line

Operator license# 32016
Operator: Pioneer Resources

Lease: Pakkebier Well # 1
County: Graham 121.55

Address: R.R. 2 - Box 47A
Phillipsburg, Kansas 67661

Well total depth 3740 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 262 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Shields Drilling Company License# 5184

Address: Shields Building, Russell, Kansas 67665

Company to plug at: Hour: 10:00 A.M. Day: 15 Month: August Year: 1997

Plugging proposal received from: Burt Beery

Company: Shields Drilling Company Phone:

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
SHIELDS DRILLING COMPANY
AUG 20 4 11 29

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [], Part [], None [X]


8-20-97

Completed: Hour: 1:45 P.M., Day: 15, Month: August, Year: 1997

Actual plugging report:
1st. Plug at 1970' w/25 sxs. - Anhydrite 1939' - 1973'.
2nd. Plug at 1170' w/100 sxs. - Dakota 876' - 1176'.
3rd. Plug at 315' w/40 sxs. - Surface pipe to 262'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2276 GL

I did [] / did not [X] observe the plugging.


(agent)
Form CP-2/3

INVOICED
DATE AUG 21 1997
INV. NO. 48837