

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22827-00-00  
Spot: NWSE Sec/Twnshp/Rge: 10-6S-22W  
1980 feet from S Section Line, 2140 feet from E Section Line  
Lease/Unit Name: R.E.T. Well Number: 1  
County: GRAHAM Total Vertical Depth: 3820 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188 8100 E 22ND ST. N. #700  
WICHITA, KS 67278

Conductor Pipe: Size feet: 8/24.15  
Surface Casing: Size 8.625 feet: 250  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 04/23/2002 1:00 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: BILL WYNN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: JAY PFEIFER

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 04/23/2002 3:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

1st. Plug at 1950' w/25 sxs.  
2nd. Plug at 1150' w/100 sxs.  
3rd. Plug at 300' w/40 sxs.  
4th. Plug at 40' w/10 sxs - 8 5/8" wiper plug.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
AUG 07 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Jay Pfeifer

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-7-02

INV. NO. 2003060183

AUG 05 2002