

6-14

6-100413

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,579 ⁰⁰⁻⁰⁰

NE SE NE /4 SEC. 10, 06 S, 22 W
3630 feet from S section line
330 feet from E section line

Operator license# 6484 Lease Rush Trust well #B-1

Operator: Anderson Energy, Inc. County Graham

Address: 200 East First Street Well total depth 3850 feet - 125.12
Suite 414 Conductor Pipe: inch @ feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 246 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: White & Ellis Drilling Company License# 5420

Address: Wichita, Kansas 67202

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Don Demell

Company: White & Ellis Drilling Company phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 3970 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1920 feet " 25 " Mousehole: sacks

3rd plug @ 1135 feet " 100 "

4th plug @ 290 feet " 40 "

5th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by:
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:00 am, Day: 14, Month: June, Year: 1990

Actual plugging report: Hole reported plugged as above.
Order 215sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2236 GL, Anhydrite depth: 1917 - 1951 feet

Did penetrate Arbuckle, cemented by Halliburton

I did[] / did not[X] observe the plugging.

INVOICED AUG 22 1990

DATE: 8-28-90 8-22-90
CONSERVATION DIVISION
Wichita, Kansas

David K. Wann P.I.R.T. II
(agent)
Form CP-2/3

INV. NO. 28131