

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01029-00-01  
Spot: SESUNE Sec/Twnshp/Rge: 33-6S-21W  
2970 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: JOHNSON Well Number: 1  
County: GRAHAM Total Vertical Depth: 1730 feet

Operator License No.: 31523 32705  
Op Name: RANEY OIL COMPANY  
Address: 3425 TAM O'SHANTER  
LAWRENCE, KS 66047

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 187 185 SX CMT  
Production: Size 5.5 feet: 3624 175 SX CMT  
Liner: Size feet:

Well Type: SWD UIC Docket No: D27093.0 Date/Time to Plug: 06/25/2002 9:00 AM

Plug Co. License No.: 31523 Plug Co. Name: RANEY OIL COMPANY

Proposal Rcvd. from: ROBERT A. WAHLMEIER Company: RANEY OIL COMPANY Phone: (785) 625-2725

Proposed Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Plugging Well plugged back to 1730' for SWD.  
Method: 5 1/2" casing perf at 1845' and circulate to surface with 300 sxs cement.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/25/2002 11:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.U. Cementer to 5 1/2" casing - squeezed casing with 200 sxs 60/40 pozmix - 10% gel with 500# hulls in cement.  
Max. P.S.I. 600#. S.I.P. 400#.  
R.U. Cementer to 8 5/8" - Pressured up to 600#.

RECEIVED  
AUG 12 2002  
08-12-02  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis Hamel by Herb Deines  
(TECHNICIAN)

JUL 16 2002

replacement card

RANEY OIL  
LAWRENCE KS 66047

33-06S-21W  
SE SW NE

# 1 JOHNSON OWWO

site: 6-1/2 N & 2-1/4 W OF NICODEMUS KS	ty: GRAHAM	API 15-065-01029			
contr: DUKE DRILLING # 4	field: MCFARLAND EXT (1/8 E)				
geol: ROGER WELTY					
fr date 03/06/95	spd date 03/12/95	drig comp 03/13/95	card issued 05/29/95	last revised 03/03/97	

ELV: 2215 KB, 2212 GL LOG  
tops.....depth/datum

PBTD .....1730 + 485  
HEEB .....3428 -1213  
TOR .....3453 -1238  
LANS .....3469 -1254  
\* ARB .....3724 -1509  
RTD OLD .....3770 -1555  
\* SAMPLE TOP

IP status:  
SWDW, CED HILL 1493-1575, 04/11/95  
CORR & INFO REL: 3/3/97 - CORR TOPS; ADDED MISC INFO  
NOTE: CORR & INFO REL: 9/2/96 - CORR WO DATES & MISC INFO; ADDED KC ELEV  
OLD INFO: OPERATOR WAS WILCOX OIL & GAS / B & R DRILLING; 1 JENKINS, SPD 02/21/48, 03/07/48 8-5/8" 187 (ALT 2), D&A, ARB, 03/07/48 (CARD ISSUED 03/10/48)  
CONTR: B & R DRILLING  
NO CORES OR TSTS

NEW INFO: FR 03/06/95, RE-ENTERED 03/12/95 WSH DWN TO 3770 DC 03/13/95 CSG: SET 5-1/2" 3769 / 175 SX, MULTI STAGE COLLAR AT 1810 / 350 SX  
(over)

COPYRIGHT 1997  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

RANEY OIL  
LAWRENCE KS 66047

33-06S-21W  
SE SW NE

# 1 JOHNSON OWWO

COMMENT: WAS API IOG-18462  
TRGT ZN: ARB, PTD 3500 (ARB), MICT - CO, PB 3650 TD, PF (KC) 3536-3538, 3541-3545, SWB DWN, REC ALL WTR, PLUG OFF ZN, PF (KC C) 3520-3522, 3539-3542, SWB DWN, REC ALL WTR, PLUG OFF ZN, PF (KC) 3500-3504, SWB DWN, REC ALL WTR, PLUG OFF ZN, SET CIBP AT 3100, PB 1730 TD, PF (CED HILL) 1493-1575, NO TRTMT, SET 2-3/8" TBG AT 1290, PKR AT 1350, COMP AS SWDW - INJECTION RATE SATISFACTORY, 4/11/95