

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01029-00-01
Spot: SESWNE Sec/Twnshp/Rge: 33-6S-21W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: JOHNSON Well Number: 1
County: GRAHAM Total Vertical Depth: 3770 feet

Operator License No.: 31523 *32705*
Op Name: RANEY OIL COMPANY
Address: 3425 TAM O'SHANTER
LAWRENCE, KS 66047

Conductor Pipe: Size feet: 8/22.53
Surface Casing: Size 8.625 feet: 187 185 SX CMT
Production: Size 5.5 feet: 3624 175 SX CMT
Liner: Size feet:

Well Type: SWD UIC Docket No: D27093.0 Date/Time to Plug: 06/25/2002 9:00 AM

Plug Co. License No.: 31523 Plug Co. Name: RANEY OIL COMPANY

Proposal Rcvd. from: ROBERT A. WAHLMEIER Company: RANEY OIL COMPANY Phone: (785) 625-2725

Proposed: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugging: Well plugged back to 1730' for SWD.
Method: 5 1/2" casing perf at 1845' and circulate to surface with 300 sxs cement.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/25/2002 11:00 AM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.U. Cementer to 5 1/2" casing - squeezed casing with 200 sxs 60/40 pozmix - 10% gel with 500# hulls in cement.
Max. P.S.I. 600#. S.I.P. 400#.
R.U. Cementer to 8 5/8" - Pressured up to 600#.

RECEIVED

JUL 30 2002
07-30-02
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed Dennis J. Hamel
(TECHNICIAN)

INVOICED

DATE 7-30-02
INV. NO. 2003060620

Form CP-2/3

JUL 16 2002

replacement card

RANEY OIL
LAWRENCE KS 66047

33-06S-21W
SE SW NE

1 JOHNSON OWWO

site: 6-1/2 N & 2-1/4 W OF NICODEMUS KS	city: GRAHAM	API 15-065-01029
contr: DUKE DRILLING #4	field: MCFARLAND EXT (1/8 E)	
geol: ROGER WELTY		
ir date 03/06/95	spd date 03/12/95	drig comp 03/13/95
	card issued 05/29/95	last revised 03/03/97

		A	

ELV: 2215 KB, 2212 GL LOG
 tops.....depth/datum

PBTD1730 + 485
 HEEB.....3428 -1213
 TOR3453 -1238
 LANS3469 -1254
 *ARB3724 -1509
 RTD OLD3770 -1555
 *SAMPLE TOP

IP status:
 SWDW, CED HILL 1493-1575, 04/11/95
 CORR & INFO REL: 3/3/97 - CORR TOPS; ADDED MISC INFO
 NOTE: CORR & INFO REL: 9/2/96 - CORR WO DATES & MISC INFO; ADDED KC ELEV
 OLD INFO: OPERATOR WAS WILCOX OIL & GAS / B & R DRILLING, 1 JENKINS, SPD 02/21/48, 03/07/48 8-5/8" 187 (ALT 2), D&A, ARB, 03/07/48 (CARD ISSUED 03/10/48)
 CONTR: B & R DRILLING
 NO CORES OR TSTS

NEW INFO: FR 03/06/95, RE-ENTERED 03/12/95 WSH DWN TO 3770 DC 03/13/95 CSG: SET 5-1/2" 3769 / 175 SX, MULTI STAGE COLLAR AT 1810 / 350 SX (over)

COPYRIGHT 1997
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

RANEY OIL
LAWRENCE KS 66047

33-06S-21W
SE SW NE

1 JOHNSON OWWO

COMMENT: WAS API IOG-18462
 TRGT ZN: ARB, PTD-3500 (ARB), MICT - CO, PB 3650 TD, PF (KC) 3536-3538, 3541-3545, SWB DWN, REC ALL WTR, PLUG OFF ZN, PF (KC C) 3520-3522, 3539-3542, SWB DWN, REC ALL WTR, PLUG OFF ZN, PF (KC) 3500-3504, SWB DWN, REC ALL WTR, PLUG OFF ZN, SET CIBP AT 3100, PB 1730 TD, PF (CED HILL) 1493-1575, NO TRTMNT, SET 2-3/8" TBG AT 1290. PKR AT 1350, COMP AS SWDW - INJECTION RATE SATISFACTORY, 4/11/95