

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-065-22,383-00-00

LEASE NAME Johnson A

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

3630' Ft. from S Section Line

2310' Ft. from E Section Line

SEC. 33 TWP. 6S RGE. 21 (X) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 7-15-87

Plugging Completed 7-15-87

LEASE OPERATOR K & E Petroleum, Inc.

ADDRESS 300 Hardage Center Wichita, KS 67202

PHONE#(316) 264-4301 OPERATORS LICENSE NO. 5267

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District 6, Hays, Kansas

Is ACO-1 filed? yes If not, is well log attached? no

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	261	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped mud to 3710', set 1st plug from 3710' to 3601' w/ 25 sxs; pump mud to 1900', set 2nd plug from 1900' to 1800 w/25 sxs, pumped mud to 1130'; set 3rd plug from 1130' to 730' w/100 sxs; pumped mud to 270' set 4th plug from 270' to 110' w/40 sxs; pumped mud to 40', set wiper plug, cemented from 40' to surface w/ 10 sxs; 15 sxs rat-hole

(If additional description is necessary, use BACK of this form.)

All Cement 60-40 posmix, 6% gel, 3% cc

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center Bldg. Wichita, KS

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1987

STATE CORPORATION COMMISSION

Carmen L. Adelson

JUL 27 1987 Notary Public Carmen L. Adelson

My Commission Expires: 8-21-90

CONSERVATION DIVISION
 Wichita, Kansas

Form CP-4
 Revised 07-86

7-27-87

