

15-065-60037-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Graham County. Sec. 36 Twp. 6 Rge. (E) 21(W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW

Lease Owner The Palmer Oil Corporation

Lease Name Parker Well No. 1

Office Address 415 Union National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 4/29 19 46

Application for plugging filed 4/29 19 46

Application for plugging approved 4/29 19 46

Plugging commenced 4/29 19 46

Plugging completed 4/29 19 46

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Kerr

Producing formation Depth to top Bottom Total Depth of Well 3794 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation                   | Content | From    | To   | Size               | Put In | Pulled Out |
|-----------------------------|---------|---------|------|--------------------|--------|------------|
| Surface, water, sand & clay | Water   | Surface | 168' | 10 $\frac{3}{4}$ " |        |            |
| Shale & Shells              |         | 168     | 1400 |                    |        |            |
| Sand & Lime                 |         | 1400    | 1800 |                    |        |            |
| Lime & Shale                |         | 1800    | 3415 |                    |        |            |
| Lime                        |         | 3415    | 3672 |                    |        |            |
| Conglomerate                |         | 3672    | 3770 |                    |        |            |
| Arbuckle Lime               |         | 3770    | 3794 |                    |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Well was drilled to total depth of 3794'. Circulated at total depth with 11-5 drilling mud - layed down 3626' drill pipe and set back 168' forced wooden plug to base of 10 $\frac{3}{4}$ " surface pipe plug 163'-168' displaced drilling mud at top of plug with 15 sax slurry cement poured through 4 $\frac{1}{2}$ " drill pipe, layed down balance of drill pipe - forces top plug down to 25' - suspended plug with soft laid line and anchored same at bottom of derrick base - mixed 10 sax cement and filled from plug to top of surface casing at grave level. Open at top for future inspection



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Palmer Oil Corporation  
Address 415 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.


Otto H. Schnepel (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Otto H. Schnepel

Union National Bank Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of June

My commission expires 3/21/49



7-15-46