

15-065-02691-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Graham County. Sec. 34 Twp. 6S Rge. (E) 21 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NW

Lease Owner Nadel & Gussman

Lease Name Pennington Well No. 1

Office Address Mutual Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 5-10-43 19

Application for plugging filed 5-11-43 19

Application for plugging approved 5-11-43 19

Plugging commenced 5-12-43 19

Plugging completed 5-12-43 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation None Depth to top Bottom Total Depth of Well 3865 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Arbuckle</u>	<u>Water</u>	<u>3814</u>	<u>3865</u>	<u>10-3/4"</u>	<u>635</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Drill pipe was run to bottom of hole and hole circulated with heavy rotary mud. As pipe was laid down stopped and filled hole with heavy mud at each 500 feet. Bridge plug pushed to near bottom of surface casing at 635'. Pumped 15 sacks of cement on top of bridge. Filled hole with mud to 26'. Set bridge. Filled solid with cement from 26' to 6'. Welded plate over top of surface casing.

PLUGGING
FILE SEC. 34 6 R 21 W
BOOK PAGE 74 LINE 21

MAY 20
CONSERVATION DIVISION
WICHITA, KANSAS

5-20-43

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Nadel & Gussman
Address Mutual Building, Tulsa, Oklahoma

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

C. M. Copeland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. M. Copeland

(Address)

SUBSCRIBED AND SWORN to before me this 19th day of May, 19 43

My commission expires July 22nd, 1943

W. E. Griffin
Notary Public.

This report prepared and signed by:

19-4174

6-42-6M

C. M. Copeland C. M. Copeland, Supt.
Halmerich & Payne, Inc.
Drilling Contractors.