

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,737-00-00

LEASE NAME Rouback

WELL NUMBER 1

1650 Ft. from S Section Line

660 Ft. from ^W Section Line

SEC. 5 TWP. 6 RGE. 22 (~~XX~~ or (W))

COUNTY Graham

Date Well Completed 6/25/94

Plugging Commenced 6/25/94

Plugging Completed 6/25/94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hess Oil Company

ADDRESS P. O. Box 1009, McPherson, KS 67460

PHONE#(316) 241-4640 OPERATORS LICENSE NO. 5663

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/25/94 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filled? yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3750 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation Surface	Content	From 213	To 0'	Size 8-5/8"	Put in 213'	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged with 200 sx 60/40 Pozmix, 6% gel, 1/4# floseal thru-out, as follows: 25 sx @ 2000', 100 sx @ 1190', 40 sx @ 265', 10 sx @ 40', 10 sx mousehole, 15 rathole. P.D. @ 11:15 p.m., 6/25/94.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hess Oil Company

STATE OF KANSAS

COUNTY OF

McPHERSON RECEIVED

ss.

Dick Hess

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address)

same

SUBSCRIBED AND SWORN TO before me this 15th day of July 19 94

My Commission Expires: _____

