

15-065-02237-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 4 Twp. 6 Rge. 22 (E) W (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE SE SW

Lease Owner Wilcox Oil Company

Lease Name Hannah Well No. 1

Office Address 310 W. 6th St., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 8th 1947

Application for plugging filed January 15th 1948

Application for plugging approved January 16th 1948

Plugging commenced January 17th 1948

Plugging completed January 24th 1948

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	200'	
				5 1/2"	3671'	2002'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with crushed rack to 3510' dumped 5 sacks of cement at 3510'. Shot off pipe at 3100'. Pipe would not start. Shot off pipe at 2000'. Pulled 5 1/2" casing. Filled hole with mud to 200'. Dumped 15 sacks cement at 200'. Filled hole with mud to 25'. Dumped 25 sacks cement for cap.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to E. E. Holden
Address Box 810 Bristow, Oklahoma 4-27-48

STATE OF Oklahoma COUNTY OF Tulsa ss.


J. L. Keefe (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] (Address) Box 744 Tulsa Okla

SUBSCRIBED AND SWORN to before me this 26th day of April, 1948

Clara Alworth Notary Public.

My commission expires 8-31-51 22-287



Wilcox Oil Co.
Rouback, Hannah, #1

SESESW
Sec. 4 Twp. 6 Rge. 22
County: Graham, Kansas

Total Depth: 3673'
Comm: 8/24/47 Comp: 9.8/47

Top Topeka Lime - 3284
" Lansing K.C. - 3508

Casing
10 Jts. 8 5/8" Set at 200'
116 Jts. 5 1/2" Set at 3671'

Cement
150 Sx
100 Sx

Formation:	Depth:
Surface Clay, Shale	30'
Sand	40
Sand & Shale	180
Shale	200
Shale & Shells	350
Shale	555
Sand	585
Shale & Shells	915
Shale & Sand	935
Sand	1080
Shale & Sand	1205
Shale, Shells & Sand	1460
Shale & Shells	1485
Sand	1670
Red Bed, Shale & Shells	1790
Shale & Red Bed	1880
Shale & Shells	1929
Anhydrite	1990
Shale & Shells	2290
Shale & Lime	2310
Lime	2350
Shale & Lime	2915
Lime	3066
Lime & Shale	3235
Lime	3320
Lime, Broken	3367
Lime	3672
Steel line correction	3675
Derrick Floor correction	3673

STATE OF KANSAS)
) SS
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Larry French

Subscribed and sworn to before me this 19th day of April, 1948.

Clara L. Luman
Notary Public

My Comm. Expires 6/17/50



4-27-48

PLUGGING
FILE SEC 4 76 R 770
BOOK PAGE 9 LINE 14